

Bk 117


See Page 74 - Line between 13824 not
within limit with the line bet 24825 470
See Page 102. No Variation given at the
corner Osces 5, 6, 7 & 8

Transcript for Washington, made
July 29th, 1873,
W. B. W.

A. H. Simmons having been
Employed by George William Deputy
Surveyor as compassman do solemnly
swear that I will well and faithfully
and to the best of my skill and ability
execute the duties as compassman
according to the Laws of the United
States and the instructions furnished
by the Surveyor General of Oregon

Subscribed and sworn
to before me this 13th
day of May A.D. 1873
C. Moore
Notary Public

A H Simmons



2
P. 472
blank

473

no

I, Erchas H. Love, and Benjamin
Baxter do solemnly swear
that I will faithfully execute
the duties of Chain Carrier
that I will level the chain
on uneven ground and plumb
the tall pins ^{no} either by dropping
or sticking, the same that
I will report the true distance
on line to all notable objects
and the true length of all
lines measured by me to
the best of my skill and ability

E. H. Love,

B. Baxter

Sworn and subscribed to before
me this 27th Sept 1873

J. P. Deery
Notary Public

Field notes To complete
the exterior lines of Township
5 & 6 N. R. 37 & 38 East of
the Wadumette Meridian by
Grover Williams Dep. Surv.
under his Contract No.

Dated 1872

Assisted by E. M. Love and
B. Bayter Chumman
Andrew Jasper Teagman
and R. Hays Aronson
and A. H. Linnins Compsman
Work commenced September
29th 1872

Township 6 N. R. 37 E. Will. Mer.

Begin at the established corner
for Sec 19, 24, 25 & 30 on the
Range line between Ranges
37 & 38 E Township 6 N. Witness
trees standing and agree with
description furnish me by

Township 6N R. 37E

519A

	6	5	4	3	2	1				
7	8	9	10	11	12					
18	64	17	64	16	60	15	57	14	52	13
69	68	63	59	56	52					
19	67	20	63	21	59	22	56	23	51	24
67	66	62	58	55	51					
30	66	29	62	28	58	27	54	26	50	25
65	65	61	57	54	49					
31	64	32	60	33	57	34	53	35	49	36

Subdivisions of Township G.W.R.
37 E Willamette Mermetian

North between sees 35 & 36
Var 2 1/2° E

- 20.00 Wood road E. W.
- 2003 Log Cabin 30 lks W.
- 40.00 Set post for 1/4 Sec. Cor. from which
a Lumber 12 in dia bears S 25° E 5 lks dist
" " " 14 " " " S 18° W 8 " "

67.00 Decred Mill

- 80.00 Set post for Cor to sees 25, 26, 35 & 36
a white fir 6 in dia bears N 16° E 8 lks dist
" " " 9 " " " N 11° W 29 " "
" " " 5 " " " S 15° W 14 " "
" " " 8 " " " S 10° E 27 " "

Good rolling soil Good
Lumber Spruce Pine Birch & Alder

East on Random line between sees 25 & 36

- 40.00 Set post for temporary 1/4 Sec Cor
- 80.18 Intersect E. boundary of Twp. 27 lks
N of the Cor for sees 25, 30, 31 & 36

521
 T. C. W. R. 37 E Hill. Dur.

	from which Cor I run N $89^{\circ}48'W$ on a true line between Sec 25 & 26
19.16	Lumber Road N W & SE
24.60	Spr. branch 50 lks W full N. W.
40.09	Set post for $\frac{1}{4}$ Sec: Cor. from which a white Fir 8 in dia bears N $10^{\circ}W$ 29. lks d.
	" Lumarac 14 " " " S $42^{\circ}W$ 26 " "
57.70	Spr. branch 1 lks wide full NW.
54.80	Ascend
56.80 89.78	Lumber Road N. W. & S E To corner
	North between Secs 25 & 26 at $21\frac{1}{2}^{\circ}E$
25.70	Spr branch 10 lks wide full N $70^{\circ}W$
26.20	Lumber Road Ascend
40.00	Set post for $\frac{1}{4}$ Sec Cor from which a Lumarac 12 ⁱⁿ dia bears N $10^{\circ}W$ 65 lks dia " Fir 8 " " " S $20^{\circ}E$ 20 " "
68.50	Ridge & Road
77.50	Cross gulch & ascend
80.00	Set post for the Cor to Secs 23, 24, 25 & 26 a white Fir 8 in dia bears S $26^{\circ}E$ 11 lks dist.

532

T. C. R. 37 E Hill, Mex.

A white Fir 6 in dia bears S 45° W. 12 lbs dist
 .. Fir Stump 10 N 27° W 35
 Sand Hills Lumber Pine Fir & Lammrock
 Oct. 17, 1872

East on a Random line between Secs 24 & 25

- 40.00 Set post for temporary 1/4 Sec. Cor.
- 80.27 Intersect Low. line 30 lbs S of the Cor of
for Secs 19, 24, 25 & 30 fourth's Cor. B run
S. 89° 46' W on a true line between Secs 24 & 25
- 1.77 Summit of Ridge
- 34.00 Bottom of gulch falls N.E. ascend
- 40.14 Set post for 1/4 Sec. Cor. in mound with pits
- 45.10 Enter timber
- 62.00 Top of divide between Cottonwood & Mill Cos.
- 78.00 Timber Road N.W. & S.E.
- 80.27 To Corner
numerous Lumber Pine Fir & Spruce

North between Secs 23 & 24

Var 20° E

- 2.50 Timber Road N.W. & S.E. ascend
- 28.00 Summit of ridge descend

T. C. N. R. 37 & Hill. Mer.

40.00	Set post for $\frac{1}{4}$ Sec. Cor. from which a Red Fir 12 in dia bears N 80° E 64 lks dist " " " 16 " " " N 65° W 52 " "
50.20	Limber Road E & W
76.00	leave timber
80.00	Set post in mound with pits for Cor to Secs. 13, 14, 23 & 24 Sand hummocks Limber Pine Fir & Lianas
East on a Random line between Secs. 13 & 24	
40.00	Set post for temporary $\frac{1}{4}$ Sec. Cor.
79.70	Intersect the Cor for Secs 13, 18, 19 & 24 45 lks S; from which I run South 89° 41' W. on tra line between Secs 13 & 24
39.85	Set post for $\frac{1}{4}$ Sec. Cor. from which a Fir 6 in dia bears N 14° E 20 lks dist " " 12 " " " " S 20° W 8 " "
67.56 79.70	leave timber ascend to corner
North between Secs 13 & 14 Var 20.15° E	
32.00	Flat Ridge
40.00	Set post for $\frac{1}{4}$ Sec Cor from which

T. C. W. R. 37 E Hill, Tex.

A White fir 10 in dia bears N 80° E 14 lks dist

" Red " 9 " " " " N 65 E 16 " "

51.80

Intersect N boundary of State line

15.97 chs. N. of the 40 mill post set

post for closing Cor for fractional Secs

13 & 14 from which

A Pine 10 in dia bears N 15° E 71 lks dist

" " 5 " " " " S 6° N 23 " "

Land more level Soil good heavy undergrowth

Oct. 18th 1872

North between Secs 34 & 35

Bear 21° 35' E

Ascend steep Rocky Hill

11.00 Cross N Fork of Cottonwood & ascend

40.00 set Stone 18x15x10 mound of Rock for ^{Cor} 1/4 Sec

51.50 A Spr 50 lks East of line

80.00 set post for Cor to Secs 26, 27, 34 & 35

A pine 24 in dia bears N 30° E 220 lks dist

" " 18 " " " " S 15° E 97 " "

Land mountainous Good Grass Lumber Pine & Fir

T. C. W. R. 37 & Well. Mer.

	East on a Run down line between Sec 26 & 35
40.00	Set post for temporary $\frac{1}{4}$ Sec. Cor.
79.80	Intersect N & S line 5 6 lks S. of the Cor for Secs 25, 26, 35 & 36 from this cor. Down S $89^{\circ}36'$ W. on a tree line between Sec 26 & 35
19.80	Ascend
32.30	Brush fence N W & S E
39.90	Set post for $\frac{1}{4}$ Sec Cor from which a Larreae 8 or 10 lks S $13^{\circ}E$ / 5 lks dist " Red Fir 5 " " " " N $21^{\circ}W$ 24 " "
62.30	Brush Fence N & S.
56.30	Fence 7' Weather S $50^{\circ}E$
48.00	Low timber
73.80	A Beans House N 8 lks dist
79.80	The corner Sec 26, 27, 34 & 35 Soil good Rolling Timber Pin Fir
	North between Secs 26 & 27 Car $21^{\circ}E$
1.00	Cross Road to timber
11.00	Cross Road to timber
11.25	Brush Fence

S. C. N. R. 37. E. Well. Mer.

- 40.00 Set post for $\frac{1}{4}$ Sec Cor from which
a Lammrae / 10 cinders bears $570^{\circ} E$ 24 lks dist
" Red Fir 4 " " " " $N10^{\circ} W$ 15 " "
- 68.50 Graded timber Road S & W
- 78.50 Bottom of Mill Corion N & Corft
- 71.00 Ascend live timber
- 80.00 Set stone in mound $7 \times 12 \times 20$ for Cor
to Secs 22, 23, 26 & 27
Sand Mountainous Lumber Fir & Pine
-
- East on Random line between Secs 23 & 26
- 40.00 Set post for temporary $\frac{1}{4}$ Sec Cor
- 80.20 Intersect N & S line 60 lks S of the Cor for
Secs. 23, 24, 25 & 26 from which Cor. Run
 $S 89^{\circ} 34' W$ on a true line between Secs 23 & 26
- 12.90 Lumber Road N W & S E
- 37.80 Lumber Road N W & S E
- 40.10 Set Rock $6 \times 10 \times 6$ mound of Rock with
pits for $\frac{1}{4}$ Sec. Cor.
- 80.20 The Cor for Secs 22, 23, 26 & 27
Sand Ruckey Lumber Fir & Pine
Oct 19, 1872

L. C. R. 37 E. Hill, Wis.

North between Secs 22 & 23

Ros 2 1/2 E

27.90 Lumber Road N 50° E Ascend

35.70 Summit Pike's Peak Ridge 800ft descend

40.00 Set post for 1/4 Sec Cor edge of timber

A Red Fir 20 in dia bears N 20° E 44 lks dist

" " " 12 " " " N 33 W 92 " "

60.70 Bottom of Dry Gulch 800ft., Ascend, leave timber

80.70 Set Rock 14x16x20 around of Rock for the Cor. to

Secs 14, 15, 22 & 23. — Land Rough

Lumber Pine Fir & Laminae

East on a random line between Secs 14 & 23

40.00 Set post for temporary 1/4 Sec Cor

80.60 Intersect N & S line 57 lks N. of the Cor of

Secs 13, 14, 23 & 24 from which Cor Low N 89

36 W on a true line between Secs ¹⁴ 23 & ²³ 28

40.30 Set post for 1/4 Sec Cor from which

A Laminae. 20 in dia bears N 50° 3 19 lks dist

" Fir 8 " " " S 75° 23 9 " "

54.30 Leave Timber

80.60 The Cor for Sec 14. 15 22 & 23, Land, Valley

528

T. L. R. 37. E Well, Meridian

North between Secs 14 & 15,

Var. $21^{\circ} E$

37.00 Ascend Summit of Ridge 500 ft

40.00 Set Stake mound & pits for $\frac{1}{4}$ Sec, Cor,

51.75 Enter sec N. boundary of State 16, 15 Chs

N. of 3rd mile post, set Rock 6x7x18

for the cor. of fractional Secs 14 & 15

Land Montanans Good Buckley & Sons

Lumber Pine & Fir } Oct 21st 1872

North between Secs 33 & 34

Var $21\frac{3}{4}^{\circ} E$

6.50 Cross Ridge & descend steep hill

40.00 Set post & rock in mound of Rock for $\frac{1}{4}$ Sec Cor

51.50 Round E & W. Ascend

72.00 Cross ridge

80.00 Set post & Stone mound & pits for the

Corner of Secs 27, 28, 33 & 34

Land Montanans Bunch Good

East on a section line between Secs 27 & 34

40.00 Set post for temporary $\frac{1}{4}$ Sec, Cor,

523

T. C. R. 37 E Hill, Meridian

- 7970 Intersect N & S line 46 S of the Cor for Secs 26, 27, 34 & 35 from this Cor I run S 89° 40' W on a true line between Sec 27 & 34
- 39.85 Set post for 1/4 Sec Cor round Rock on hill with fence S - descend
- 7970 The Cor for Secs 27, 28, 33 & 34
Sand Kelly, no timber, Good Grass
-
- North between Secs 27 & 28
Bar 2 1/2° E
- 6.25 Cross Gullet & ascend
- 40.00 Set Stone 12x13x24 around of Stone for 1/4 S,
- 58.50 Timber road
- 59.57 Summit of ridge descend
- 80.00 Set post & mark Stone round & pits for the Cor to Secs 21, 22, 27 & 28
Sand hills no timber Good Grass
-
- East on remainder line between 22 & 27
- 40.00 Set post for 1/4 Sec Cor,
- 8030 Intersect N & S line 37 lks N of the Cor for Secs 22, 23, 26 & 27 from which I run N 89° 44' W

T & R 87 E Hill, Meridian 530

40.15 on a true line between Sies 22 & 24
 40.15 Set post & stone 18x8x36 round of stone
 for 1/4 Sec Cor. a cherry bush S. side of mound
 73.50 Road S 70° E
 78.00 bottom of gulch ascend
 80.30 The Cor for Sies 21, 22, 27 & 28
 Sand hilly, no timber, Good Grass

North between Sies 21 & 22

Var 2 1/2 E

4.25 foot of hill road E & W
 5.00 Spr. branch 3 lks wide runs N & W, ascend
 40.00 Set post & stone 4x8x12 round stone & pits
 for 1/4 Sec. Cor
 52.00 Ridge & ascend
 80.00 Set stone 10x15x30 pits for cor to Sies
 15, 16, 21, & 22
 Sand very hilly Good Grass

East on random line between Sies 15 & 22

40.00 Set stone for temporary 1/4 Sec. Cor.
 79.78 Intersect N & S line 27 lks W of the Cor for

531

T C N R 37, E Hill. Meridian

for 14, 15, 22 & 23 from this Cor & N 89°

48' N on a true line between Secs. 15 & 22

39,89 Set Stone 14x15x20 on steep side hill
face N. for 1/4 Sec. Cor.

59,89 Summit of ridge descend

77,84 Road N.W. & E. descend

79,78 The Cor for Secs 15, 16, 21 & 22,
Sand hill w timber Good Grass

North between Secs 15 & 16

Cor 2 1/2 E

7,00 Summit of ridge descend falls N W

21,00 Road E & W

40,00 Set Stone 12x18x36 for 1/4 Sec. Cor.

52,13 Entrance to boundary State 16.86 Chs
N. of post 38 mill & set stone 6x9x13
for the Cor to fractional Sec 15 & 16
Sand Hill Good brush Grass

Oct 22, 1872

North between Secs 32 & 33

Cor 2 1/2 E

543

T. C. R. 37 E Hill Meridian

Ascent Hill

- 20.00 Cross timber road N.W.
- 34.00 cross Spur to Ascent, enter timber
- 36.00 cross Gulch leave timber
- 40.00 Set post in mound of stone for $\frac{1}{4}$ Sec. Cor.
- 47.00 N Fork of Cottonwood Cr. 10 lks wide, ascent
- 80.00 Set Stone 15 x 17 x 24 mound & pits for Cor
to Secs 28, 29, 32 & 33

Sound Hill Timber Pine & Fir

East on meridian line between Secs 28 & 33

- 40.00 Set Stone for temporary $\frac{1}{4}$ Sec. Cor.
- 79.70 Enter at N & E line 34 lks N of Cor for
Secs 27, 28, 33 & 34 from which I run
N 89° 45' W on a true line between Secs 28 & 33
- 9.70 Gulch 200 ft Ascent
- 39.85- Set Stone 5 x 8 x 12 mound & pits for $\frac{1}{4}$ Sec. Cor.
- 52.00 Cross Gulch
- 70.70 Cross Ridge Decent
- 79.70 The Cor. for Secs 28, 29, 32 & 33

Land numerous no timber

Good Grass of the Bunch variety

T. G. R. 37 E. Hill Meridian

North between Secs 28 & 29
 Par $21^{\circ} E$

24.00 Cross Ridge soft falls N W
 40.00 Set stone $8 \times 16 \times 24$ mound stone for $\frac{1}{4}$ Sec. Cor.
 80.00 Set stone $4 \times 24 \times 30$ mound & pits for
 Cor to Secs 20, 21, 28 & 29
 Land very hilly w timber Good Grass

East on random line between Secs 21 & 28

40.00 Set post for temporary $\frac{1}{4}$ Sec Cor
~~79.30~~ Intersect N & S line, 30 lb S of
 the Cor for Secs 21, 22, 27 & 28 from
 which Cor & run $S 89^{\circ} 47' W$ on true line
 between Secs 21 & 28

39.65 Set post & marked stone mound & pits
 for $\frac{1}{4}$ Sec Cor.

41.00 Cross Ridge
 42.50 Cross Road

79.30 The Cor for Secs 20, 21, 28 & 29
 Land hilly w timber Good Grass

55
 T.C. N.R. 37 E Hill. Meridian

North between Secs 20 & 21

Cor 2 1/2 E

- 21.50 Cross road valley to timber
 24.00 Cross ridge & descend
 40.00 Set Stone 10x12x14 for 1/4 Sec. Cor.
 51.80 Deep Canion Cr. 10 lks wide flows & ascend
 55.30 Grade Road East
 80.00 Set Stone 6x8x13 mound & pits for
 Cor to Secs 16, 17, 20 & 21
 Sand Mountains Small timber or Crs.

East on same line between Secs 16 & 21

- 40.00 Set Stone for temporary 1/4 Sec. Cor.
 79.50 Intersect N & S line 49 lks N. of Cor. for
 Secs 15, 16, 21 & 22 from which Cor & run
 N 89° 39' W on true line between Secs 16 & 21
 79.78 Set Stone 2x6x15 mound of Stone for 1/4 Sec. Cor.
 56.41 Cross dry gulch
 65.00 Cross ridge
 79.50 The Cor for Secs 16, 17, 20 & 21
 Sand Hills no timber Good Grass

T. C. R 37 E Will. Juridians

North between Secs 16 & 17

Var $2\frac{1}{2}^{\circ}$ E

- 11.50 Summit of Ridge descend
 13.00 Cross rail fence E to W
 40.00 Set stone $15 \times 17 \times 20$ mound & pits for $\frac{1}{4}$ S.E.
 52.50 Enter sec N boundary State 16.0 s. cho
 West of 37 mile post. set stone
 $12 \times 14 \times 18$ for cor to fractional Secs 16 & 17
 Sand hilly no timber Good grass
 Oct 23rd 1872

North between Secs 31 & 32

Var $2\frac{1}{2}^{\circ}$ E

- 10.00 Road to timber
 30.60 Cross fence of Duer's field
 40.00 set post mound & pits for $\frac{1}{4}$ Sec Cor.
 46.00 In Duer's Drummy 50 lbs W.
 62.75 Cross fence and live field
 80.00 set post mound & pits for Cor to Secs
 29, 30, 31 & 32.

Soil Good no timber Good grass

T 6 NR 37 E Hill Meridian ⁵³⁸

- East on a random line between Secs 29 & 32
- 40.00 Set post for temporary $\frac{1}{4}$ Sec Cor
- 80.30 Intersect N & S line 56 lks S. of Cor
for Secs 28, 29, 31 & 32 from which Cor.
I run S 89° 36' W on a true line between
Secs 29 & 32
- 40.15 Set Post & mark Stone mound & pits for $\frac{1}{4}$ S.C.
- 62.15 Cross Ridge
- 68.07 road to timber
- 71.20 Cottonwood Cr 15 lks falls W
- 80.30 The Cor for Secs 29, 30, 31 & 32
Secs 29 & 30 rate to timber Good Grass

- West on random line between Secs 30 & 31
- 40.00 set Stone for temporary $\frac{1}{4}$ Sec Cor
- 80.42 Intersect N. boundary of T 6 N, 44 lks
W of the Cor for Secs 25, 30, 31 & 36 from
this Cor. I ran N 89° 41' E on a true line
between Secs 30 & 31
- 40.21 set post mound & pits for $\frac{1}{4}$ Sec Cor
- 41.21 Old road N. S.
- 53.12 Top of Hill Decend

7577
 W R 27 E Hill Memorial

80,412 The Cor for Secs 29, 30, 31 & 32
 Sand hills 2nd rate Good Grass

North between Secs 29 & 30
 Cor 21° E

1.00 Cross fence enter field

4.00 bottom enter Young Orchard

7.40 Cr. 12 lbs wide full NW

8.00 leave bottom ascend

23.00 Cross road

28.00 Spr branch 1 lbs wide flows W.

40.00 Set post marked stone mound & pits for $\frac{1}{4}$ Sec

80.00 Set Stone 8x10x15 in mound & pits
 for Cor to Secs 19, 20, 29 & 30

Second rate sold Good Grass no timber

East on random line between Secs 20 & 29

40.00 Set Stone for temporary $\frac{1}{4}$ Sec, Cor.

79.70 Intersect N & S line 31 lbs ^{S.} of the Cor for

Secs 20, 21, 28 & 29 from this Cor. & ran

S 89° 47' W on a true line between Secs 20 & 29

39.85 Set Stone 4x6x15 mound & pits for $\frac{1}{4}$ Sec Cor

533

Loc R R 37 E Hills, Minnesota

45.70 Cross ridge

59.70 Cross gulch

79.70 The Cor for Secs 19, 20, 29 & 30

Soil 2nd rate Good Grass no timber

Western section line between Secs 19 & 30

40.00 Set stone for temporary $\frac{1}{4}$ Sec. Cor.

79.95 Intersect W. boundary of Town, 67 lks S

of the round Cor. for Secs 19, 24, 25 & 30

(post gone) from this Cor & run $89^{\circ} 31' E$

on a true line between Secs 19 & 30

17.45 Cross fence

39.93 Set post marked stone monument pits for $\frac{1}{4}$ Sec Cor

42.00 In Kennis's House 5150 lks distant

44.00 Cottonwood Cr. 13 lks wide

60.95 Sewer field Cross fence

79.95 The Cor for Secs 19, 20, 29 & 30

Soil 2nd rate no timber Good grass

North between Secs 19 & 20

Cor. $21\frac{3}{4}^{\circ} E$

10.06 Cross ridge

530

T. C. W. R. 37 E Well Meridian

40.00 Set Stone monument & pits for 1/4 Sec, Cor,

45.00 Cross road to timber

46.00 Cross fence enter field
road

77.58 Cross to timber

78.75 Irrigating ditch

80.00 Set Stone 8x16x20 for Cor to Sec

17, 18, 19, 20

Soil 2nd rule note timber Good grass

East on remainder line between Secs 17 & 20

40.00 Set Stone for temporary 1/4 Sec, Cor,

79.87 Intersect N & S 35 lks W of Cor for Secs
16, 17, 20 & 21 from which Cor & run N.

89°45' W, on a true line between Secs 17 & 20

6.87 Cross ridge

39.93 Set Stone 6x8x12 mound of stone for 1/4 Sec, Cor

57.70 Irrigating ditch ascend

72.2 Cross Cr 18 lks thick

74.77 recross Cr leave bottom ascend

79.87 The Cor. for Secs 17, 18, 19 & 20

Soil 2nd rule small timber along Cr.

5.10

Y C R R 37. E Hill Mound

West on random line between Secs 18 & 19

40.00
40.00
79.50
79.50

Set post for temporary 1/4 Sec Cor.
Intersect Turn, line at the Cor. for Sec
13, 18, 19 & 24 from this Cor. Run E on a
true line between Secs 18 & 19

5.25
5.25
12.30
12.30
16.00
16.00
20.25
20.25
39.50
39.50

Cross fence mound
Cross Cr 20 lks with run W
Cross Cr 2 lks with run W
Cross fence

45.00
45.00
60.00
60.00
61.50
61.50
74.35
74.35
77.50
77.50
79.50
79.50

Set Stone 6x8x14 mound & pits for 1/4 Sec. Cor.
In Marchant's house bears S 4 lks distant
Cross fence enter field
Cross fence leave field
Digging ditch
Cr. 2 lks wide
The Cor for Secs 17, 18, 19 & 26.
Soil 1/2 rate ?? Oct 24th 1872

North between Secs 17 & 18

.60
60
3.30
3.30

Jan 20th E
Cliff 12 ft mound enter bottom
Cr. flows W 15 lks wide

511

10.00 Enter June
 40.00 Set Stone 6x12x18 for 1/4 Sec Cor
 52.20 Pulverize W boundary of State 16 88 chs
 W 36 mile post, set Stone 6x8x13 fo
 cor to fractional Secs 17 & 18
 Sand rolling 1st rate

General Description

This Township is much cut with deep
 canyons which bear N & SE The soil
 on the ridges is generally good
 Eastern portion is high up on the
 Blue Mountains. The Western is more
 level being nearer the foot of the
 mountain. The ravines are not so ^{deep} ^{and}
 heavy, excellent soil, is being rapidly
 settled. The timber consists of Fir
 Larch Pine Spruce Birch Alder
 Cottonwood & willow in the
 western portion of township
 Completed Oct 25 1872

Y. S. R. 3 E Hill Meridian

General Description

These four sections are the only ones of any value in the Township. There is about 40. acres of swamp prairie in Sec 8 about 80 acres in Sec 7. The timber surrounding is excellent.

Pine Fir Linnaceae
Spruce & willow

I George William Deputy Surveyor do solemnly swear that in pursuance of a contract with W. H. Odell Surveyor General of the public lands of the United States in the State of Oregon bearing date the 20th day of July 1872 and in strict conformity to the Laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully surveyed the Exterior and Subdivisional lines of Township 5 North Range 37 East, the Exterior and Subdivisional lines of Fractional Townships 6 North Ranges 37 & 38 East and the Subdivisional lines of Fractional Township 5 North Range 38 East ^{in the State of} Oregon aforesaid and do further solemnly swear that the foregoing are the true and original field notes of such survey.

George William
Deputy Surveyor

Subscribed & sworn to
before me this 6th day
of May A. D. 1873

W. H. Odell
Surveyor General

584

585

List of Persons Employed to
assist in running measuring or
marking the lines and corners described
in the foregoing field notes showing
the respective capacities in which
they acted

E H Love & B Baxter Chairman
Richard Hays Assessor
Andrew Jasper Flagman
A H Simmons Comptroller

We hereby certify that we have appointed
Geo Williams, deputy surveyor, in
surveying the exterior boundaries and in subdividing
Townships Number 5 & 6 N R 37 & 38 E and
four sections in Township 5 N 38 E, of the Willamette
Meridian Territory of Oregon and that said
Townships have been in all respects, to the
best of our knowledge and belief well
and faithfully surveyed and the boundary
monuments planted according to the instructions
furnished by the Surveyor General,

E H Love, Chairman

B Baxter ..

R Hays Assessor

Andrew Jasper Flagman

A H Simmons Comptroller

Given and subscribed to before me
on this 24th day Dec 1872

O P Lacey
Notary Public

We the undersigned Bondsmen in the Contract No. 176 made between George Williams Deputy Surveyor and the Surveyor General of the United States for the State of Oregon bearing date the 20th day of July 1873 hereby consent to the substitution of fractional Township 5. & 6. North Range 38 East. Surveyed instead of Township 4 North Range 37 East left unsurveyed by reason of unfitness; And we hold ourselves in every respect liable under said Contract with said Substitution as under the original Contract
G. Williams

Mr S. C. Adams the other Bondsmen on the above mentioned contract is out of the State, he being in Cincinnati Ohio and will not return the present year.

L. H. Williams
Dep. Sur.

Salem, May 7th 1873.

586

587

U.S. Surveyor General's Office
Eugene City Oregon
September 1st 1873

The foregoing field notes of the Survey of
the ^{4th quarter} Subdivisional lines of T. 6 N R. 30
37 & 38 East fractional T. 5 N R
37 East and T. 5 N R 38 East
(fractional) Willamette Mer-
idian Oregon executed by
George Williams US deputy Sur-
veyor under contract No 176
bearing date July 20th 1872
having been carefully
examined the necessary
corrections and any plannings
made the said field notes
and the survey they con-
tain are hereby approved

W. H. Colwell
US Survey Genl.