

"B" ORIGINAL

FIELD NOTES

OF THE SURVEY OF THE

STATE

and

INDEX DIAGRAM.

RESURVEY OF PART OF OREGON AND WASHINGTON BOUNDARY;

RESURVEY OF PART OF WEST BOUNDARY;

SURVEY OF PART OF EAST BOUNDARY;

AND

SURVEY OF PART OF SUBDIVISION

OF

TOWNSHIP 6 NORTH, RANGE 39 EAST

Of the WILLAMETTE Meridian,

In the State of WASHINGTON

EXECUTED BY

ROY T. CAMPBELL, U. S. Cadastral Engineer

In the capacity of U. S. Surveyor, under Special Instructions dated April 17, 1929, issued by the United States Surveyor General to govern surveys included in Group No. 130, which were approved by the Commissioner of the General Land Office, May 11, 1929, and Assignment Instructions dated June 1, 1931.

R. T. C.

Survey commenced July 5, 1931

Survey completed August 13, 1931

FIELD NOTES

OF THE SURVEY OF THE

DATE

and

INDEX DIAGRAM.

Township 6 North, Range 39 East

13 ⁶ 7-18-31 7-18-31	43 ⁵ 7-15-31 7-15-31	37 ⁴ 7-11-31 7-11-31	33 ³ 7-9-31 7-9-31	28 ² 7-8-31 7-8-31	22 ¹ 7-6-31 7-6-31	19
45	44	39	34	29	24	
16 ⁷ 8-11-31 8-11-31	46 ⁸ 8-8-31 8-8-31	40 ⁹ 8-6-31 8-6-31	35 ¹⁰ 8-4-31 8-4-31	30 ¹¹ 7-29-31 7-29-31	25 ¹² 7-28-31 7-28-31	20 7-24-31
48	47	41	36	32	26	
18 ¹⁸ 8-11-31 8-10-31	50 ¹⁷ 8-9-31 8-7-31	42 ¹⁶ 8-6-31 8-6-31	37 ¹⁵ 8-4-31 8-3-31	33 ¹⁴ 7-29-31 7-26-31	27 ¹³ 7-28-31 7-26-31	22 7-26-31
11	8	7	5	4	2	
19	20	21	22	23	24	
30	29	28	27	26	25	
31	32	33	34	35	36	

Handwritten notes on the right side of the table.

Faint text at the bottom of the page, likely bleed-through from the reverse side.

RESURVEY OF PART OF OREGON AND WASHINGTON BOUNDARY.

000

309

Chains

from which

A fir, 14 ins. diam., bears N. 70° E., 56 lks. dist., mkd. L 4 S 18 B T.

A fir, 18 ins. diam., bears N. 53° W., 35 lks. dist., mkd. L 5 S 18 B T.

Descend 105 ft. over broken southwesterly slope.

83.25 Enter heavy timber, bears NW. and SE.; descend 10 ft. over rolling bottom land.

84.39 Paradise Creek, 15 lks. wide, course N. 35° W.; over bottom land.

87.30 Leave bottom land, bears NW. and SE.; ascend 265 ft. over broken northeasterly slope.

100.10 The closing cor. of Tps. 6 N., Rs. 38 and 39 E., hereinafter described; on summit of spur, which slopes N. 15° E. Thence, retrace on Oregon and Washington boundary.

Descend 115 ft. over northwesterly slope.

103.20 Ascend 205 ft. over broken northeasterly slope.

108.90 Spur, slopes N.; along broken N. slope.

118.20 Spur, slopes N. 20° W.; descend 115 ft. over northwesterly slope.

122.15 Ravine, course N.; ascend 210 ft. over broken northeasterly slope.

132.30 The 46 mile monument, which is a partly decayed fir post, 6 ins. sq., 3 ft. high, loosely set in durable mound of stone, 4 ft. base, 3 ft. high, marked W on N., O on S., and 46° L 1864 on E. and W. faces, and witnessed as described in the official record, except the bearing tree in Washington is 20 ins. diam., bears N. 10° E., 56 lks. dist. and the bearing tree in Oregon is 24 ins. diam., bears S. 6° W., 20 lks. dist. I mark 46 M in addition to the original marks on both trees.

At point for monument,

Set an iron post, 3 ft. long, 3 ins. diam., 36 ins. in the original mound of stone to top, for 46 mile monument, with brass cap mkd.

46 M
W
O

1931

from which;

new bearing trees,

A fir, 32 ins. diam., bears S. 26° E., 44 lks. dist., mkd. 46 M O B T.

A fir, 7 ins. diam., bears N. 5° W., 17 lks. dist., mkd. 46 M W B T.

This monument stands on summit of spur, which slopes N.

RESURVEY OF PART OF OREGON AND WASHINGTON BOUNDARY.

Chains Land, mountainous and level.
 Soil, sandy loam, stony; 3d and 4th rate.
 Timber, fir, yellow pine, and cottonwood; undergrowth, 2d growth fir and pine, small alder, vine maple, Oregon grape, rose, bunch grass, sumac, greasewood, and small cherry.

The point for $\frac{1}{4}$ sec. cor. established for sec. 1 and 6 determined by the original mound of stone, witnessed as described in the official record, except the bearing bearing tree in sec. 1 bears S. 18° W. 155 lks. dist.

Resurvey of part of W. bdy. of Tps. 6 N., R. 39 E.
 Dependent resurvey, superseding the survey executed by Francis F. Loehr, U. S. Deputy Surveyor, in 1879.

Random Line

From the cor. of Tps. 6 and 7 N., Rs. 38 and 39 E., South, bet. secs. 1 and 6.

38.66 The point for $\frac{1}{4}$ sec. cor. bears W., 1.46 chs. dist.

77.96 The point for cor. of secs. 1, 6, 7, and 12 bears W., 0.26 ch. dist.

The N. half of this line is S. 2° 10' W., 38.69 chs.; and the S. half is S. 1° 45' E., 39.32 chs.

From the point for sec. cor.,

South, bet. secs. 7 and 12.

37.87 The point for $\frac{1}{4}$ sec. cor. bears W., 9.34 chs. dist.

76.23 The point for cor. of secs. 7, 12, 13, and 18 bears W., 13.30 chs. dist.

The N. half of this line is S. 13° 51' W., 39.00 chs.; and the S. half is S. 5° 54' W., 38.56 chs.

From the point for sec. cor.,

South, bet. secs. 13 and 18.

29.96 The closing cor. of Tps. 6 N., Rs. 38 and 39 E., on Oregon and Washington boundary, bears W., 1.93 chs. dist.

This line is S. 3° 41' W., 30.02 chs.

True Line

From the cor. of Tps. 6 and 7 N., Rs. 38 and 39 E., which is an iron post, 3 ins. diam., 28 ins. above ground and in mound of stone, firmly set, marked and witnessed as described in the record of the "Resurvey of part of W. bdy. of T. 7 N., R. 39 E.", Book "A", this group,

S. 2° 10' W., on W. bdy. of sec. 6.

Descend 110 ft. over rugged southwesterly slope, through scattering timber and undergrowth,

6.05 Ravine, course NW.; ascend 245 ft. over rugged northwesterly slope.

12.50 Spur, slopes W.; descend 165 ft. over rugged southwester-

CERTIFICATE OF UNITED STATES SURVEYOR.

I, Roy T. Campbell, U. S. Cadastral Engineer, District Cadastral Engineer for Washington

bearing date of the 17th day of April, 1929, I have well, faithfully, and truly in my own proper person, and in strict conformity with said instructions, the Manual of Surveying Instructions, and the laws of the United States, surveyed all those parts or portions of

Township No. 6 North, Range No. 39 East

of the Willamette

Meridian, in the State of Washington

and preliminary data and on the dates shown the foregoing field notes as having been executed by me, and under my direction; and that all the corners of said survey have been established and perpetuated in strict accordance with the Manual of Surveying Instructions, and the special written instructions of the District Cadastral Engineer for Washington

and in the specific manner described in the field notes, and that the foregoing are the original field notes of such survey.

Olympia, Washington, May 25, 1932.

Roy T. Campbell, U. S. Cadastral Engineer

APPROVAL.

Office of U. S. Supervisor of Surveys Denver, Colorado, AUG 2 1932

The foregoing field notes of the survey of Township No. 6 North, Range No. 39 East of the Willamette Meridian, Washington,

executed by Roy T. Campbell, U. S. Cadastral Engineer

under his special instructions dated April 17, 1929, having been critically examined, and the necessary corrections and explanations made, the said field notes, and the surveys they describe, are hereby approved.

U. S. Supervisor of Surveys

I certify that the foregoing transcript of the field notes of the above-described surveys in has been correctly copied from the original notes on file in this office.

U. S. Surveyor General.