

FIELD NOTES.

On the survey of the *Subdivisional*
 Lines of *Township 6 South*
Range 35 East Willamette Meridian,
 Oregon, as surveyed by *Herwan D. Gradon*
 U. S. Deputy Surveyor, under his Contract No. *499*
 dated *March 11*" 188*4*

Survey commenced *Sept. 14th* 188*4*
 Survey completed *Sept 25th* 188*4*

NAMES AND DUTIES OF ASSISTANTS.

....., Compassman.
Andy Keater, Chainman.
Jesse B. Stinehour, Chainman.
, Chainman.
, Chainman.
Henry Canaday, Axeman.
Calvin Wilson, Axeman.
, Flagman.

PRELIMINARY OATHS OF ASSISTANTS.

We, *Andy Heater* and *Jesse B. Stinchow*

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the *subdivisional line*

lines of *S 6 S -*

R 35 E - Willamette Meridian, Oregon.

Andy Heater, Chainman.

Jesse B. Stinchow, Chainman.

_____, Chainman.

_____, Chainman.

Subscribed and sworn to before me, this *16*

day of *May* ¹⁸⁸⁴

[SEAL.] *A. D. Gradon*
Notary Public

We, *Henry Canaday* and *Calvin Wilson*

do solemnly swear that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability

in the survey of the *subdivisional lines of*

S 6 S - R 35 E - Willamette Meridian, Oregon.

Henry Canaday, Axeman.

Calvin Wilson, Axeman.

Subscribed and sworn to before me, this *16*

day of *May* ¹⁸⁸⁴

[SEAL.] *A. D. Gradon*
Notary Public

INDEX.

375

Referring the Lines to the Pages of the Field Notes.

T. *C S* R. *35 C* Will. Mer.

6	123	5	89	4	68	3	45	2	25	1
<i>121</i>		<i>119</i>		<i>88</i>		<i>66</i>		<i>44</i>		<i>22</i>
7	116	8	85	9	64	10	42	11	20	12
<i>114</i>		<i>112</i>		<i>84</i>		<i>62</i>		<i>40</i>		<i>18</i>
18	111	17	81	16	60	15	38	14	15	13
<i>108</i>		<i>107</i>		<i>80</i>		<i>59</i>		<i>36</i>		<i>13</i>
19	105	20	78	21	56	22	34	23	11	24
<i>102</i>		<i>100</i>		<i>77</i>		<i>55</i>		<i>32</i>		<i>9</i>
30	98	29	74	28	52	27	30	26	7	25
<i>96</i>		<i>95</i>		<i>73</i>		<i>51</i>		<i>29</i>		<i>4</i>
31	92	32	71	33	48	34	26	35	2	36

Meanders of Page to

Meanders of Page to

96

476

Subdivisions of T. 6 S. R. 35-E
 Willamette Meridian, Oregon.

bears N 14° W 11 lks. dist.
 marked 1/4 S B T

A black pine 8 ins diam
 bears S 16° W 12 lks. dist.
 marked 1/4 S. B. T.

69.00

A Creek 8 lks. wide runs
 S W about 300 ft. below ridge
 ascend about 125 ft. to

79.66

The cor. to secs. 29, 30, 31 & 32
 Land mountainous 79.66 chs
 Soil 2nd rate

Densely covered with forests
 of black pine fir and tamarack
 79.66 chs.

Nest on a random line
 bet. secs. 30 & 31
 Va 20 1/4° E

40.00

Set temp. 1/4 sec. cor.

60.52

Intersect N bdy. of township

482

Subdivisions of T. 6 S. R. 35-E
Willamette Meridian, Oregon.

79.72

about 350 ft. below divide.
The cor. to sects. 19, 20, 29 + 30
Land mountainous 79.72 chs
Soil 2nd rate
Densely covered with forests
of black pine, fir and tamarack
79.72 chs.

West on a random line
bet. sects. 19 + 30

Va. 20 1/4° E

40.00

60.40

Set temp. 1/4 sec. cor.
Intersect N. bdy. of township
53 lks S. of the cor. to sects
19, 30 24 + 25. which is a
post 4 ft. long 4 in square
set firmly in the ground
marked

of 6 S S 19 on N. E.
R 35-E S 30 on S. E

1899

Subdivisions of T. 6 S. R. 35-E

Willamette Meridian, Oregon.

S 23° W 14 lks. dist marked
1/4 S.B.T.

69.00
79.84

A trail, course N.
A point about 600 ft. above
Creek
The cor to sect. 17, 18, 19 & 20
Land mountainous 79.84
Soil 2nd & 4th rate.
Densely covered with forests
of fir, pine & tamarak 79.84

West on a random line
bet. sects. 18 & 19
Va 20 1/4 ° E

40.00
60.64

Set temp. 1/4 sec. cor.
Intersect W. bdy. of twp
44 lks S. of the cor. to sect
18, 19, 13 & 24 which is
a post 4 ft. long 4 in sq.
set firmly in ground

Subdivisions of T. 6 S. R. 35 E
 Willamette Meridian, Oregon.

Land mountainous 80.30 chs
 Soil 2nd rate. Densely covered
 with forests of fir pine
 and Lamanack

Sept. 24-1884

Nest on a random line bet.
 secs. 7 & 18

Va 20 1/4° E

40.00

Set temp. 1/4 sec. cor.

60.68

Intersect W. bdy. of township
 62 lks. S of the cor. to secs.
 7, 18 12 & 13. which is a
 post 4 ft. long 4 in square
 set firmly in ground,
 marked

T. 6 S S 7 on N E

R 35-E S 18 on S E

R 34 E S 13 on S W and

S 12 on N W. faces, with

495

Subdivisions of T. 6 S. R. 35-E
Willamette Meridian, Oregon.

2 notches on N & 4 notches
 on S. edge, from which
 A spruce 10 ins diam base
 N 42° E 8 lks. dist. marked
 T 6 S R 35-E S 7 B J

A spruce 10 ins diam base
 S 48° E 9 lks. dist. marked
 T 6 S R 35-E S 18 B J

A spruce 10 ins diam base
 S 32° W 12 lks. dist. marked
 T 6 S R 34-E S 13 B J

A spruce 10 ins diam base
 N 66° W 10 lks. dist. marked
 T 6 S R 34-E S 12 B J

Thence run

S 89° 33' E on a true line
bet sec. 7 & 18. Va 19° 40' E

20.68 Descending through timber
 bet a post 3 ft long 3 ins
 square 24 ins in the ground
 for 1/4 sec. cor. marked 1/4 S

121
500

Subdivisions of T. 6 S R. 35 E
Willamette Meridian, Oregon.

West on a random line
bet. secs 6 & 7

N 20 1/4 ° E

40.00
60.92

Set temp. 1/4 Sec Cor.
Intersect N. bdy. 12 lks. S. of
the cor. to sec. 6, 7, 1 & 12 which
is a basalt stone 13x12x10 ins
set firmly in ground, mark
ed with 1 notch on N &
5-notches on S. edges;
from which -

A pine 10 ins diam bears
N 52 ° E 24 lks. dist. marked
T 6 S R 35 E S 6 B. J.

A pine 10 ins diam bears
S 12 ° E 40 lks. dist. marked
T 6 S R 35 E S 7 B. J.

A fir 11 ins diam bears
S 62 ° W 14 lks. dist. marked
T 6 S R 34 E S 12 B. J.

A fir 10 ins diam bears

Subdivisions of T. 6 S. R. 35 E
Willamette Meridian, Oregon.

N 33° W 10 lbs. dist marked
Y 6 S R 34 E S 1 B. T.

Thence run

S. 89° 54' E. on a true line
bet. secs. 6 & 7. Va 19 1/2° E

Descending through timber

20.92

20.92

Set a post 3 ft. long 3 ins square
24 ins in the ground for
1/4 sec. cor. marked 1/4 S. on
N. face, from which

A pine 5 ins diam bears

N 29° W 23 lbs. dist marked 1/4 S B. T.

A pine 6 ins dia bears S 63° W

1/4 lbs. dist. marked 1/4 S B. T.

57.00

51.00

A creek 8 lbs. wide flows N.
about 500 ft. below last sec.
Cor.

Ascend about 200 ft. to

60.92

60.92

The cor. to secs. 5, 6, 7 & 8

Land mountainous 60.92 lbs

Soil 2nd rate. Densely covered

FINAL OATH OF DEPUTY SURVEYOR.

I, Arman D. Gradon

United States Deputy Surveyor, do solemnly swear that in pursuance of

instructions received from James L. Tolman

U. S. Surveyor General for Oregon, bearing date of the 11

day of March, 1884, I have well, faith-

fully and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the Laws of the United States, surveying all those

parts or portions of the subdivisional lines of Township 6 South Range 35 East

Willamette Meridian, in the State of Oregon, as are represented in the foregoing Field Notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual, Printed Instructions, the Special Written Instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the Field Notes, and that the foregoing are the true Field Notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an Act of Congress approved August 8th, 1846.

Arman D. Gradon
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this 11

day of Oct 1884

R. J. Stator
Notary Public
for Oregon

OFFICE U. S. SURVEYOR GENERAL,

Portland, Oregon, Nov. 24, 1884

The following Field Notes of the Survey of the

Subdivisional lines of
Township 6 South Range
35 East Will. Abey Or.

executed by Herman D. Graden

under his Contract No. 499, dated March

11th 1884, having been critically examined,

the necessary corrections and explanations made, the said

Field Notes and the survey they describe are hereby approved.

James C. Tolman

Surveyor General.