

FIELD NOTES

OF THE

REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS,

TOWNSHIP 6 SOUTH, RANGE 33 EAST,

Lined area for field notes.

Of the WILLAMETTE Meridian,

In the State of OREGON

EXECUTED BY

Craig L. Wanless, Cadastral Surveyor

Under special instructions dated May 3, 19 57, approved May 6, 1957,

_____, which provided for the surveys included under ~~U.S. Survey~~/Group
Number 350, and assignment instructions dated September 21, 19 77.

Survey commenced October 4, 19 77

Survey completed October 26, 19 77

INDEX DIAGRAM

Township 6 South, Range 33 East,

6	5	4	3	2	1
	<u>8</u>	<u>7</u>	<u>5</u>		<u>5</u>
7	8	9	10	11	<u>4</u> 12
					<u>3</u>
18	17	16	15	14	13
		<u>6</u>			
19	20	21	22	23	24
30	29	28	27	26	25
	<u>7</u>				
31	32	<u>6</u> 33	34	35	36
<u>3</u>	<u>2</u>	<u>2</u>	<u>1</u>	<u>1</u>	

Remonumentation of Certain Original Corner Points,
T. 6 S., R. 33 E., Willamette Meridian, Oregon

CHAINS

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, and in a mound of stone, 2 ft. base, to top, with brass cap mkd.

T 6 S R 33 E
¼ $\frac{S\ 32}{S\ 5}$
T 7 S
1977

from which new bearing trees

A pine, 10 ins. diam., bears N. 14° W., 32 lks. dist., mkd. ¼ S32 BT.

A pine, 10 ins. diam., bears S. 27° W., 47 lks. dist., mkd. ¼ S5 BT.

Deposit corner stone alongside iron post.

The ¼ sec. cor. of secs. 6 and 31, on the S. bdy. of the Tp., monumented with the original unmarked basalt stone, 13 x 10 x 10 ins., firmly set 4 ins. in the ground, in a collar of stones, from which the remains of the original bearing trees:

A pine stump, size indeterminate, bears N. 40° E., 43 lks. dist., with fragmentary scribe marks visible on open blaze. (Record, N. 20° E.)

A decayed pine stump, size indeterminate, bears S. 45° E., 11 lks. dist., no marks visible.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 6 S R 33 E
¼ $\frac{S\ 31}{S\ 6}$
T 7 S
1977

from which new bearing trees

A fir, 7 ins. diam., bears N. 70° E., 6 lks. dist., mkd. ¼ S31 BT.

A fir, 12 ins. diam., bears S. 45° W., 73 lks. dist., mkd. ¼ S6 BT.

Deposit corner stone alongside iron post.

East Boundary, T. 6 S., R. 33 E.,
Willamette Meridian, Oregon

(Remonumenting a corner established by Frank W. Campbell,
U. S. Deputy Surveyor, in 1883)

The cor. of secs. 7, 12, 13, and 18, on the E. bdy. of the Tp., determined at record distance from the remains of the original bearing trees:

Remonumentation of Certain Original Corner Points,
T. 6 S., R. 33 E., Willamette Meridian, Oregon

CHAINS

A spruce, 14 ins. diam., bears N. 19° E., 32 lks. dist., with healed blaze.

A spruce snag, 13 ins. diam., bears S. 32° E., 31 lks. dist., with fragmentary scribe marks visible on partially healed blaze. (Record, S. 38° E.)

A spruce snag, 10 ins. diam., bears S. 48° W., 14 lks. dist., with scribe mark R visible on partially healed blaze. (Record, S. 38° W.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 6 S	
R 33 E	R 34 E
S 12	S 7
S 13	S 18
1977	

from which new bearing trees

A spruce, 9 ins. diam., bears S. 10° E., 52 lks. dist., mkd. T6S R34E S18 BT.

A spruce, 11 ins. diam., bears S. 60° W., 27½ lks. dist., mkd. T6S R33E S13 BT.

A fir, 13 ins. diam., bears N. 67½° W., 79 lks. dist., mkd. T6S R33E S12 BT.

Subdivisions, T. 6 S., R. 33 E.,
Willamette Meridian, Oregon

(Remonumenting corners established by Frank W. Campbell,
U. S. Deputy Surveyor, in 1883)

The ¼ sec. cor. of secs. 11 and 12, monumented with the original unmarked basalt stone, 15 x 10 x 10 ins., loosely set 1 in. in the ground, from which the remains of the original bearing trees:

A larch snag, 12 ins. diam., bears N. 25° E., 42 lks. dist., with scribe marks ¼ S BT visible on open blaze.

A larch snag, 12 ins. diam., bears S. 33° W., 37 lks. dist., no marks visible.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 6 S R 33 E	
¼	
S 11	S 12
1977	

from which new bearing trees

CERTIFICATE OF SURVEY

(I) ~~(We)~~, Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) ~~(We)~~ have remonumented certain original corner points, township 6 south, range 33 east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), ~~(us)~~ and under (my) ~~(our)~~ direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

January 16, 1978
(Date)

Craig L. Wanless
(Cadastral Surveyor)

(Date)

(Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT
~~Washington, D.C.~~
Denver, Colorado

The foregoing field notes of the remonumentation of certain original corner points, township 6 south, range 33 east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

JAN 23 1980
(Date)

J. J. [Signature]
(Chief, Division of Cadastral Survey)

Chief, Cadastral Survey Examination and Approval Staff

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in _____, is a true copy of the original field notes.

(Date)

(Chief, Division of Cadastral Survey)