

FIELD NOTES.

On the survey of the *Subdivisional*
 Lines of *Township 6 South*
Range 35 East Willamette Meridian,
 Oregon, as surveyed by *Herwan D. Gradon*
 U. S. Deputy Surveyor, under his Contract No. *499*
 dated *March 11*" 188*4*

Survey commenced *Sept. 14th* 188*4*
 Survey completed *Sept 25th* 188*4*

NAMES AND DUTIES OF ASSISTANTS.

....., Compassman.
Andy Keater, Chainman.
Jesse B. Stinehour, Chainman.
, Chainman.
, Chainman.
Henry Canaday, Axeman.
Calvin Wilson, Axeman.
, Flagman.

PRELIMINARY OATHS OF ASSISTANTS.

We, *Andy Heater* and *Jesse B. Stinchow*

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the *subdivisional line*

lines of *S 6 S -*

R 35 E - Willamette Meridian, Oregon.

Andy Heater, Chainman.

Jesse B. Stinchow, Chainman.

_____, Chainman.

_____, Chainman.

Subscribed and sworn to before me, this *16*

day of *May* ¹⁸⁸⁴

[SEAL.] *H. D. Gradon*
Notary Public

We, *Henry Canaday* and *Calvin Wilson*

do solemnly swear that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability

in the survey of the *subdivisional lines of*

S 6 S - R 35 E - Willamette Meridian, Oregon.

Henry Canaday, Axeman.

Calvin Wilson, Axeman.

Subscribed and sworn to before me, this *16*

day of *May* ¹⁸⁸⁴

[SEAL.] *H. D. Gradon*
Notary Public

INDEX.

375

Referring the Lines to the Pages of the Field Notes.

T. *C S* R. *35 C* Will. Mer.

6	123	5	89	4	68	3	45	2	25	1
<i>121</i>		<i>119</i>		<i>88</i>		<i>66</i>		<i>44</i>		<i>22</i>
7	116	8	85	9	64	10	42	11	20	12
<i>114</i>		<i>112</i>		<i>84</i>		<i>62</i>		<i>40</i>		<i>18</i>
18	111	17	81	16	60	15	38	14	15	13
<i>108</i>		<i>107</i>		<i>80</i>		<i>59</i>		<i>36</i>		<i>13</i>
19	105	20	78	21	56	22	34	23	11	24
<i>102</i>		<i>100</i>		<i>77</i>		<i>55</i>		<i>32</i>		<i>9</i>
30	98	29	74	28	52	27	30	26	7	25
<i>96</i>		<i>95</i>		<i>73</i>		<i>51</i>		<i>29</i>		<i>4</i>
31	92	32	71	33	48	34	26	35	2	36

Meanders of Page to

Meanders of Page to

Subdivisions of T. 6 S. R. 35-E
 Willamette Meridian, Oregon.

A fir 5 ins diam bears
 S 47° W 14 lbs. dist. marked
 T 6 S R 35-E S 35-B.T.

A fir 6 ins diam bears
 N 53° W 20 lbs. dist. marked
 T 6 S R 35-E S 26-B.T.

Land mountainous & rocky.
 Soil 2nd rate.

Densely covered with forest
 of fir, tamarack and pine
 80.00 chs.

East on a random line
 bet. secs. 25th & 36

Va. 20° E

Set temp. 14 sec. cor.

40.00

80.18

Intersect E. bdy. 37 lbs. N
 of the cor. to secs. 25+36 which
 is a post 4 ft. long 4 ins dia.
 set firmly in ground marked

Subdivisions of T. 6 S. R. 35 E
Willamette Meridian, Oregon.

~~T. 6 S. S. 30 on N E
 R 35 E S 31 on S E
 S 36 on S N. and
 S 25 on N. N. faces with
 notch on S & 5 notches on
 N. edges from which
 A black pine 4 ins dia. bears
 S 56° N 43 lbs. dist. marked
 T 6 S R 35 E S 36 B. T.
 A black pine 4 ins dia. bears
 N 38° N 76 lbs. dist. marked
 T 6 S R 35 E S 25 B. T.~~

Thence from
 N 89° 44' N. on a true line bet.
 Secs 25 & 36

to Va 20 1/4° E

Descend through timber

14.25 A Spring branch 1 1/2 k wide
 flows S.

26.10 Sharp creek 12 lbs. wide
 flows N. N. about 300 ft. below cor.

Subdivisions of T. 6 S. R. 35 E
Willamette Meridian, Oregon.

East on a random line
bet. secs. 24 & 25

Va 19° E

40.00 Set temp. 1/4 sec. cor.

79.88 Intersect E. bdy. 33 lbs.

N. of the cor. to secs. 24 & 25

~~which is a post set firmly
in ground marked~~

~~T 6 S S 19 on N E~~

~~R 36 E S 30 on S E~~

~~R 35 E S 25 on S N, and~~

~~S 24 on N N, faces with~~

~~2 notches on S & 4 notches~~

~~on N. edges - from which~~

~~A black pine 8 ins diam bears~~

~~S 1/2° N 27 lbs. dist. marked~~

~~T 6 S R 35 E S 23 B. I.~~

~~A fir 10 ins diam bears~~

~~N 10° N 30 lbs. dist. marked~~

~~T 6 S R 35 E S 24 B. I.~~

Thence Iron.

Subdivisions of T. 6 S R. 35 E
Willamette Meridian, Oregon.

Soil 2nd rate
Densely covered with forests
of pine fir & tamarack & oaks

Sept. 14 - 1884.

Cast on a random line
bet. secs. 13 & 24

Va. 20° E

40.00 Set temp. 14 sec. cor.

79.40 Intersect - E. bdy 33 lbs S
of the cor. to secs. 13 & 24 which
is a post 4 ft. long 4 ins
set firmly in ground
marked

T 6 S. S. 18 on NE

R 36 E S 19 on SE

R 35 E S 23 on SW and

S 14 on NW faces with
notch on E & 3 notches on

Subdivisions of T. 6 S. R. 35 E

Willamette Meridian, Oregon.

~~S. edges from which
A pine 13 ins diam bears
S 60° W 47 lks. dist marked
T 6 S R 35 E S 24 B J
A fir 7 ins diam bears
N 72° W 53 lks. dist marked
T 6 S R 35 E S 13 B J~~

Thence run
S 89° 46' W on a true line
bet. sec. 13 + 24

to a 20' 4" E

31.26

39.70

A fir 24 ins in diam
Set a post 3 ft. long 3 ins
square 24 ins in ground for
1/4 Sec. cor. marked 1/4 S
on N. face; from which
A tamarack 7 ins diam bears
N 90° E 14 lks. dist marked

1/4 S. B. J.

A black pine 6 ins diam bears
S 10° W 18 lks. dist marked
1/4 S. B. J.

Subdivision of T. 6 S. R. 35-E
Willamette Meridian, Oregon.

East on a random line
bet. secs. 12 & 13

Va 20° E

40.00

Set temp. 14 sec. cor.

79.28

Intersect - E. bdy. 27 lks.

S. of the cor. to secs. 12 & 13
which is a post 4 ft long
4 ins square set firmly in
the ground, marked

T 6 S S 7 on N.E.

R 35-E S 18 on S.E.

R 35-E S 13 on S.N. and

S 12 on N.N. faces; with

2 notches on N & 4 notches
on S edges; from which

A black pine 10 ins diam
bears S 34° W 45 lks dist marked

T 6 S R 35-E S 13 B.T.

A black pine 10 ins dia bears
N 74° W 32 lks. dist marked

T 6 S R 35-E S 12 B.T.

402

Subdivision of T. 6 S. R. 35-E

Willamette Meridian, Oregon.

A black pine 4 ins dia bears
S 20° E 7 lks. dist. marked

T 6 S R 35-E S 12 B.T.

A black pine 5 ins dia bears
S 52° W 15 lks. dist. marked

T 6 S R 35-E S 11 B.T.

A black pine 5 ins dia bears
N 23° W 28 lks. dist. marked

T 6 S R 35-E S 2 B.T.

Land hilly - 80.00 chs.

Soil 2nd grade

Densely covered with forest
of pine & tamarack 80.00 chs.

East on a random line
bet. secs. 1 & 12

Va 20½° E

40.00

Set temp. 1/4 sec. cov.

79.24

Intersect E. bdy. 75 lks S
of the cov. to secs. 1 & 12 which

Subdivisions of T. 6 S R. 35 E
Willamette Meridian, Oregon.

is a post 4 ft long 4 ins square set firmly in the ground, marked

T 6 S S 6 on NE
R 36 E S 7 on SE
R 35 E S 12 on SW and
S 1 on NW faces; with
1 notch on N & 5 notches
on S edges; from which
A black pine 5 ins dia bears
S 65° W 18 lbs. dist. marked
T 6 S R 35 E S 12 B. J.
A black pine 4 ins dia bears
N 35° W 34 lbs. dist. marked
T 6 S R 35 E S 1 B. J.

Thence run
S 89° 28' W. on a true line
bet secs. 1 & 12

Va 20° E
Descend through timber
17.00 A House bears S 20° W about

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by Herman D. Gradon, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the survey of the Subdivisional lines lines of Township 6 S R 35 E Willamette Meridian, Oregon, showing the respective capacities in which they acted:

- Andy Heater, Compassman.
Jesse B Stinehour, Chainman.
Henry Canaday, Chainman.
Calvin Wilson, Axeman.
Calvin Wilson, Axeman.
Calvin Wilson, Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted Herman D. Gradon, U. S. Deputy Surveyor, in surveying all those parts or portions of the subdivisional lines of Township 6 South Range 35 East Willamette Meridian, Oregon, as are represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been, in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

- Andy Heater, Compassman.
Jesse B Stinehour, Chainman.
Henry Canaday, Chainman.
Calvin Wilson, Axeman.
Calvin Wilson, Axeman.
Calvin Wilson, Flagman.

Subscribed and sworn to before me, this first day of October

[SEAL] Herman D. Gradon U. S. Deputy Surveyor

FINAL OATH OF DEPUTY SURVEYOR.

I, Arman D. Gradon

United States Deputy Surveyor, do solemnly swear that in pursuance of

instructions received from James L. Tolman

U. S. Surveyor General for Oregon, bearing date of the 11th

day of March, 1884, I have well, faith-

fully and truly, in my own proper person, and in strict conformity with
the instructions furnished by the U. S. Surveyor General for Oregon, the
Surveying Manual, and the Laws of the United States, surveying all those

parts or portions of the subdivisional lines of
Township 6 South Range 35 East

Willamette Meridian, in the State of Oregon, as are represented in the
foregoing Field Notes as having been surveyed by me and under my di-
rections; and I do further solemnly swear that all the corners of said sur-
vey have been established and perpetuated in strict accordance with the
Surveying Manual, Printed Instructions, the Special Written Instructions
of the U. S. Surveyor General for Oregon, and in the specific manner de-
scribed in the Field Notes, and that the foregoing are the *true* Field Notes
of such survey, and should any fraud be detected I will suffer the penalty
of perjury under the provisions of an Act of Congress approved August
8th, 1846.

Arman D. Gradon
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this 11th

day of Oct, 1884

R. J. Stator
Notary Public
for Oregon

OFFICE U. S. SURVEYOR GENERAL,

Portland, Oregon, Nov. 24, 1884

The following Field Notes of the Survey of the

Subdivisional lines of
Township 6 South Range
35 East Will. Abey Or.

executed by Herman D. Graden

under his Contract No. 499, dated March

11th 1884, having been critically examined,

the necessary corrections and explanations made, the said

Field Notes and the survey they describe are hereby approved.

James C. Tolman
Surveyor General.