

FIELD NOTES.

On the survey of the *Subdivisional*  
Lines of *Township 6 South Range*  
*35 1/2 East* ..... *Willamette Meridian,*  
Oregon, as surveyed by *W. B. Barr*  
U. S. Deputy Surveyor, under his Contract No. *492*  
dated *August - 22<sup>5</sup>* ..... *1883*

Survey commenced *May 3<sup>5</sup>* ..... *1884*  
Survey completed *May 10<sup>th</sup>* ..... *1884*

NAMES AND DUTIES OF ASSISTANTS.

- ....., *Compassman.*
- Albert Boenicke* ..... , *Chainman.*
- F. Meason* ..... , *Chainman.*
- ....., *Chainman.*
- ....., *Chainman.*
- A. G. Wright* ..... , *Axeman.*
- ....., *Axeman.*
- ....., *Flagman.*

1884

PRELIMINARY OATHS OF ASSISTANTS.

We, Albert Boenicke and F Meason

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the subdivisional

lines of Township 6

South Range 35 1/2 East Willamette Meridian, Oregon.

Albert Boenicke, Chainman.

F Meason, Chainman.

\_\_\_\_\_, Chainman.

\_\_\_\_\_, Chainman.

Subscribed and sworn to before me, this First

day of April 1884

[SEAL.]

W. B. Barr  
Notary Public

~~We~~ \_\_\_\_\_ and

J A G Wright, do solemnly swear that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability

in the survey of the subdivisions of Township

6 South Range 35 1/2 East Willamette Meridian, Oregon.

J A G Wright, Axeman.

\_\_\_\_\_, Axeman.

Subscribed and sworn to before me, this First

day of April 1884

[SEAL.]

W. B. Barr  
Notary Public

# INDEX.

Referring the Lines to the Pages of the Field Notes.

T. 6.8

R. 35 $\frac{1}{2}$  E

Will. Mer.

|    |    |    |    |    |    |    |    |    |
|----|----|----|----|----|----|----|----|----|
| 6  | 5  | 4  | 79 | 3  | 47 | 2  | 24 | 1  |
|    |    |    | 77 |    | 75 |    | 45 | 22 |
| 7  | 8  | 9  | 73 | 10 | 43 | 11 | 20 | 12 |
|    |    |    | 71 |    | 69 |    | 41 | 18 |
| 18 | 17 | 16 | 67 | 15 | 39 | 14 | 16 | 13 |
|    |    |    | 65 |    | 63 |    | 37 | 14 |
| 19 | 20 | 21 | 61 | 22 | 35 | 23 | 12 | 24 |
|    |    |    | 59 |    | 57 |    | 33 | 10 |
| 30 | 29 | 28 | 55 | 27 | 51 | 26 | 8  | 25 |
|    |    |    | 53 |    | 51 |    | 29 | 5  |
| 31 | 32 | 33 | 49 | 34 | 26 | 35 | /  | 36 |

Meanders of ..... Page ..... to .....

Meanders of ..... Page ..... to .....

Subdivisions of T. 6 S R. 35 1/2 E  
Willamette Meridian, Oregon.

West on a random line bet Secs. 28 and 33  
70° 21' E

40.00 Set temporary 1/4 Sec. cor.

62.50 Intersect the W boundary of the township 22 eks. S of cor to Secs 28 and 33 which is a Basalt Stone 16 x 14 x 8 ins. 11 ins in the ground marked with 1 notch on S. and 5 notches on N. edges from which

A Spruce 12 ins. diam bears N 55° E 22 eks. dist. marked T 6 S R 35 1/2 E S 28 B 9

A Spruce 30 ins. diam. bears S. 75° E 16 eks dist marked T 6 S R 35 1/2 E S 33 B 9

Thence Run

S 89° 49' E. on a true line bet Secs. 28 & 33  
70° 20' E

150 Chute 10 eks wide course N 60° W  
Ascend 450 ft. to

22.50 Set Basalt Stone 14 x 12 x 5 ins 10 ins in the ground for 1/4 Sec. cor. marked

Subdivisions of T. 6 S ..... R. 35 1/2 E  
 Willamette Meridian, Oregon.

Post on a random line bet. Secs. 21 & 28  
 Va  $20^{\circ} 15' E$

4000 Set temporary 1/4 Sec. corner

62.25 Intersect the N. boundary of the  
 Township 54 lks. S. of cor. to Secs.  
 21<sup>and</sup> 28 which is a Basalt Stone  
 $12 \times 8 \times 6^8$  ins in the ground marked  
 with 2 notches on S. and 4 notches  
 on N. edges from which

A Pine 8 ins. diam bears N 65 E

20 lks. dist marked T 5 R 35 1/2 E S 21 B 5

A Pine 12 ins. diam bears S 60 E 12

lks. dist. marked T 5 R 35 1/2 E S 28 B 5

Thence I run

S  $89^{\circ} 29' E$ . on a true line bet. Secs. 21 & 28

Va  $20^{\circ} E$

Ascend 250 ft. to

22.25 Set Iron Post 3 ft. long 3 ins. square

24 ins. in the ground for 1/4 Sec. cor.  
 marked 1/4 S. on N. face from which

Subdivisions of T. 6 S R. 35 W E  
Willamette Meridian, Oregon.

West on a random line bet Secs 16 & 21  
'va 20°, 30' E

40.00 Set temporary 1/4 Sec. cor.

62.75 Intersect the N. boundary of the township 40 lks S. of cor. to Secs 16 & 21 which is a basalt stone 12 x 10 x 8 ins 8 ins in the ground marked with 3 notches on N and S. edges from which a Fir 24 ins. diam bears N 15 E 24 lks dist. marked T6 SR 35 W E S 16 BT

A Fir 36 ins. diam bears S 40 E 30 lks dist. marked T6 SR 35 W E S 21 BT

Thence I run

S 89° 24' E on a true line bet Secs 21 & 16  
'va 20 E

Ascend 250 ft. to

22.75 Set Fir Post 3 ft long 3 ins square 24 ins in the ground for 1/4 Sec. cor. marked 1/4 S. on N. face from which a Pine 12 ins. diam bears N. 25 W

Subdivisions of T. 6 S R. 35 W E  
Willamette Meridian, Oregon.

West on a random line bet Secs. 9 & 16

va 20. 45 E

40.00 Set temporary 1/4 Sec. cor.

62.20 Intersect the N. boundary of the township 29 lks. S. of the cor. to Secs. 9 and 16 which is a Basalt Stone 18 x 9 x 9 ins 10 r ins. in the ground with 4 notches on S and 2 notches on W edges from which a Tamarac 8 ins. diam bears. N 45 E 70 lks. dist. marked To SR 35 W E S 9 B 9

A Tamarac 6 ins. diam bears S. 45 E 40 lks. dist. marked To SR 35 W E S 16 B 9

Thence I run

S 89° 46' E on a true line bet Secs 9 & 16

va 20 E

Ascend 250 ft to

77  
~~243 1/2~~

Subdivisions of T. 6 S

R. 35 1/2 E 243 B

Willamette Meridian, Oregon.

West on a random line bet Secs. 4 and 9

va 20° 30' E

40.00 Set temporary 1/4 sec. cor

62.70 Intersect the W. boundary of the township  
41 Ecs. N. of cor. to Secs. 4 and 9 which  
is a basalt stone 14 x 12 x 8 ins 10 ins  
in the ground marked with 5 notches  
on S. and 1 notch on N. edges from  
which

A Pine 17 ins diam. bears N 85 E 50

Ecs. dist marked To SR 35 1/2 E S 4 B 9

A Tamarac 8 ins. diam bears S 30 E

40 Ecs. dist marked To SR 35 1/2 E S 9 B 9

Thence I run

N 89° 38' E, on a true line bet. Secs 4 & 9

va 20° E

Ascend 300 ft to

22.70 Set Pine post 3 ft. long 3 ins. square  
24 ins. in the ground for 1/4 sec.



### FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by W. B. Burr, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the survey of the subdivisional lines of Township 6 South Range 35 1/2 East Willamette Meridian, Oregon, showing the respective capacities in which they acted:

- ....., Compassman.
- ....., Chainman.
- Albert Boenicke, Chainman.
- F. Meason, Chainman.
- ....., Chainman.
- A. G. Wright, Axeman.
- ....., Axeman.
- ....., Flagman.

### FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted W. B. Burr, U. S. Deputy Surveyor, in surveying all those parts or portions of the subdivisions of Township 6 South Range 35 1/2 East Willamette Meridian, Oregon, as are represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been, in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

- ....., Compassman.
- Albert Boenicke, Chainman.
- F. Meason, Chainman.
- ....., Chainman.
- ....., Chainman.
- ....., Axeman.
- A. G. Wright, Axeman.
- ....., Flagman.

Subscribed and sworn to before me, this Sixteenth day of June 1884

[SEAL]

W. B. Burr  
Notary Public

## FINAL OATH OF DEPUTY SURVEYOR.

I, W. B. Barr

United States Deputy Surveyor, do solemnly swear that in pursuance of

instructions received from James C. FulmerU. S. Surveyor General for Oregon, bearing date of the 22<sup>d</sup>day of August, 1883, I have well, faithfully and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the Laws of the United States, surveying all thoseparts or portions of the subdivisions of  
Township 6 South Range 35<sup>1</sup>/<sub>2</sub> EastWillamette Meridian, in the State of Oregon, as are represented in the foregoing Field Notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual, Printed Instructions, the Special Written Instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the Field Notes, and that the foregoing are the *true* Field Notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an Act of Congress approved August 8th, 1846.W. B. Barr

U. S. Deputy Surveyor.

Subscribed and sworn to before me, this Sixteenthday of June 1884W. S. Wright

County Clerk

## OFFICE U. S. SURVEYOR GENERAL,

Portland, Oregon, *Sept. 1,* 188*4*

The following Field Notes of the Survey of the  
*Subdivisions of Township*  
*6 South Range 35 1/2 East,*  
*Will. Mer., Oregon*  
executed by *Wm B. Barr*

under his Contract No. *492*, dated *August*  
*22,* 188*3*, having been critically examined,

the necessary corrections and explanations made, the said  
Field Notes and the survey they describe are hereby approved.

*James C. Tolman*  
Surveyor General.