

FIELD NOTES

Of the survey of the subdivisional
 Lines of Town 5 South, Range
35 East of, Willamette Meridian,
 Oregon, as surveyed by Refus S. Moore
 U. S. Deputy Surveyor, under his Contract No. 451
 dated June 28th, 1882

Survey commenced, August 20th 1882

Survey completed, August 30th 1882

NAMES AND DUTIES OF ASSISTANTS.

Refus S Moore, Compassman.

James Gullidge, Chainman.

John Gullidge, Chainman.

_____, Chainman.

_____, Chainman.

Joe. Parodi, Axeman.

_____, Axeman.

_____, Flagman.

PRELIMINARY OATHS OF ASSISTANTS:

We, James Guttridge
and John Guttridge

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the subdivisional
lines of Town 5 South
Range 35 East, Willamette Meridian, Oregon.

James Guttridge, Chainman.
John Guttridge, Chainman.
_____, Chainman.
_____, Chainman.

Subscribed and sworn to before me, this Fifteenth
day of August 1882

[SEAL.] Rufus D. Moore
Notary Public

We, Joseph Parodi and

_____, do solemnly swear that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability,

in the survey of the subdivisional lines of
Town 5 S. R. 35 E of Willamette Meridian, Oregon.

Joe Parodi, Axeman.
_____, Axeman.

Subscribed and sworn to before me, this Fifteenth
day of August 1882

[SEAL.] Rufus D. Moore
Notary Public

INDEX.

Referring the Lines to the Pages of the field Notes.

T. *5 South* R. *35 East* Will. Mer.

6	98	5	70	4	54	3	37	2	19	1
96	94		69		53		36		17	
7	93	8	67	9	51	10	34	11	16	12
91	89		66		49		33		14	
18	88	17	64	16	48	15	32	14	12	13
86	84		63		47		31		10	
19	83	20	62	21	45	22	29	23	9	24
80	79		60		44		28		7	
30	77	29	59	28	43	27	26	26	5	25
75	74		58		41		25		3	
31	72	32	55	33	39	34	22	35	1	36

Meanders of _____ Pages _____ to _____

Meanders of _____ Pages _____ to _____

Subdivision of T. 5 South R. 35 East
Willamette Meridian, Oregon.

dist marked J4 & R35E & S33 & J

Thence I run

S47E On a true line bet. pts. 3 & 4
4000. Set a post 3 ft. long 3 ins sq, 24 ins
Va 20° East
in ground for use, cor. marked
1/4 on W face. from which

A fir 7 ins. in dia. bears N35°E 13 lb, dist.
marked 1/4 S & J

A fir 9 ins. in dia. bears N39°W 34 lb, dist.
marked 1/4 S & J

8000 The cor to sec. 3, 4, 9 & 10

Land mountainous

Soil 2" & 3" rate

Finer pine, fir and tamarack and
some dense undergrowth of pine, fir &
tamarack.

From the standard cor to sec. 32 & 33
On the South boundary of the
township which is a post 4 ins. sq
marked J.C. F5 & R35E on N
& S33 on E and S32 on W. faces with

775

Subdivision of T. 5 South R. 35 E
Willamette Meridian, Oregon.

4 notches on E, and 2 notches on
Wedges, from which
Apr 12 ins. in dia. bears $N 3^{\circ} E$ 9 lks. dist.
marked T 5 S R 35 E S 33 B F
Apr 14 ins. in dia. bears $N 14^{\circ} W$ 31 lks. dist.
marked, T 5 S R 35 E S 32 B F

Drum

North between Secs. 32 & 33

Var. $20^{\circ} 40'$ East

21.00 Enter creek bottom bears E & W

200 ft. below standard cor

23.50 ^{Branch of} Grande Ronde river 10 lks. wide runs
East

24.50 Branch Grande Ronde River 10 lks.
wide runs East

29.00 Leave bottom bears E & W

40.00 Set a post 3 ft. long 3 ins. sq 24 ins.
in ground for $\frac{1}{4}$ sec. cor. 100 ft.
above Grande Ronde River

from which

Apr 10 ins. in dia. bears $S 77^{\circ} E$ 34 lks.
dist. marked 14 S B F

282

72

Subdivision of T. 5 South R. 35 East
Willamette Meridian, Oregon.

From the standard cor. to sea.

31 + 32 on the South boundary
of the township which is a
post 4 ins sq. - marked

f, c, T 5 - S R 35 - E on W

f 32 on E and S 31 on W faces
with 5 notches on E and 1 notch
on W. faces, from which

A tamarack 20 ins. in dia. bears N 81° E

108 lbs. dist, marked T 5 - S R 35 - E S 32 B F

A tamarack 20 ins. in dia. bears N 58° W 159 lbs.

dist, marked T 5 - S R 35 - E S 31 B F

I run

North between seas. 31 + 32.

To 20° 30' East

40,00 Set a post 3 ft. long 3 ins. sq 24 ins
in ground for 1/4 sec. cor. - marked
1/4 S on W. face, from which

A pine 10 ins. in dia. bears N 53° E 31 lbs.

dist - marked 1/4 S B F

A tamarack 24 ins. in dia. bears N 65° W

29 lbs. dist, marked 1/4 S B F

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by Rufus S. Moore, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the survey of the Subdivisional lines of Town 5 South Range 35 East of Willamette Meridian, Oregon, showing the respective capacities in which they acted:

- James Guttridge, Compassman.
James Guttridge, Chainman.
John Guttridge, Chainman.
Joseph Parodi, Chainman.
Joseph Parodi, Axeman.
Axeman.
Flagman.

FINAL OATHS OF ASSISTANTS

We hereby certify that we assisted Rufus S. Moore, U. S. Deputy Surveyor, in surveying all those parts or portions of the Subdivisional lines of Town 5 South of Range 35 East of Willamette Meridian, Oregon, as are represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

- James Guttridge, Compassman.
James Guttridge, Chainman.
John Guttridge, Chainman.
Chainman.
Chainman.
Joe Parodi, Axeman.
Axeman.
Flagman.

Subscribed and sworn to before me, this Twenty First day of November 1882

[SEAL.] Rufus S. Moore Notary Public

FINAL OATH OF DEPUTY SURVEYOR.

I, Rufus S. Moore
 United States Deputy Surveyor, do solemnly swear that in pursuance of in-
 structions received from James C. Tolman
 U. S. Surveyor General for Oregon, bearing date of the Twelfth
~~Twenty~~ day of June, 1882 I have well, faith-
 fully and truly, in my own proper person, and in strict conformity with
 the instructions furnished by the U. S. Surveyor General for Oregon, the
 Surveying Manual, and the laws of the United States, surveying all those
 parts or portions of The Subdivisional line of
Township 5 South. Range 35 East
 Willamette Meridian, in the State of Oregon, as are represented in the fore-
 going Field Notes as having been surveyed by me and under my directions;
 and I do further solemnly swear that all the corners of said survey have been
 established and perpetuated in strict accordance with the Surveying Manual,
 printed instructions, the special written instructions of the U. S. Surveyor
 General for Oregon, and in the specific manner described in the field notes,
 and that the foregoing are the *true* field notes of such survey, and should
 any fraud be detected I will suffer the penalty of perjury under the pro-
 visions of an Act of Congress approved August 8, 1846.

Rufus S. Moore
 U. S. Deputy Surveyor.

Subscribed and sworn to before me, this 10th
 day of February, 1883
Bamford Robb
 Notary Public

311

Office U. S. Surveyor General,

Portland, Oregon, June 5, 1883

The following Field Notes of the Survey of the

Subdivisions of Twp. 5 South
Range 35 East, Will. Mer.,
Oregon

executed by Rufus S. Moore

under his Contract No. 457, dated 12th

June 1882, having been critically examined, the
necessary corrections and explanations made, the said field notes
and the survey they describe, are hereby approved.

James C. Tolman
Surveyor General.