

## Oregon and Washington Boundary Line.

	<p><b>Bearings:</b></p> <p>To small abutting rock, 1/2 distance from top of ridge, N.77°15' E., dist. 20 chs. Edge of large rock, N.80°13'W., dist. 5 chs. Center of top of projecting rocks, S.73°04' E., dist. about 25 chs. Rock abutting from ridge, S. 68°34' W., dist. 12 chs. Made excavation 3 ft. deep. Deposited charred stake &amp; bones. Planted a charred willow post, 8 ft. long &amp; 8 ins. sq.; trimmed at upper end. Top beveled; marked on N. face "W", on S. "Q", on E. "46° L 1864" and on W. "9 M". Built a durable mound about post principally of stone and covered with soil and then seeded. The trench &amp; pits as usual. This mound is well located for making known the Oregon and Washington Bdy. in this vicinity and is about 6 miles from mouth of canyon.</p>
9 M. 1864 May 28	
S.14-15.	<p>Proceeding thence E.; ascend and cross top of ridge &amp; descend abrupt rocky side to ravine, 10 chs. from 9th mile post, intersect N. &amp; S. line bet. Secs. 14-15. Set post on rocky side of hill, built mound, erected post; dug pits, etc.; thence descending over rocky side, end of 40 chs. on side of ridge near the top. Marked parallel. Made excavation, deposited charred cherry stakes. Planted a willow post, 6 ft. long &amp; 5 ins. sq., upper end trimmed; top bevelled; ground end charred. Placed two large stones near the post; threw up a small mound (the inclination of the hill being too great for a large one). Dug deep rectangular trench &amp; 3 pits, the lower or E. one being omitted. Post marked on W. face 1/2 M., bearings to ledge of rock on ridge, N.29°26' E., dist. say 50 chs. about 10 chs. S. this ridge descends &amp; makes a gap, then rises in continuation of the ridge to the S.S.E.</p>
1/2 M.	
10 M.	<p>Descending the steep sides of the ridge, cross a small valley bet. high ridges and which valley is 1/4 mile wide; on W. side of a small stony hill, put in the 10th Mile post. Made excavation, 3 ft. deep; soil stony; deposited 2 charred white thorn stakes; planted post, 8 ft. long</p>