

Oregon and Washington Boundary Line.

	<p>To lone tree on Walla Walla River; N. 54°31'E., dist. 3 miles.</p> <p>Center of bend in Walla Walla River, N. 5°04'W., dist. 2 miles.</p> <p>Made excavation, 2 ft. deep; deposited a white cobble stone of quartz. Planted a post, 6 ft. long & 4 ins. sq.; trimmed; top beveled; ground end charred; marked on W. side "½ M." Built mound of earth, 6 ft. sq. at base and 3 ft. high, tapering to post; earth packed & sodded. Dug as usual, rectangular trench, 2 spades wide & 18 ins. deep; also 4 pits at cardinal points of mound.</p> <p>Crossing foot spurs of ridge; descend to small ravine; ascend; cross low ridge, bearing down N.N.E., descend to flat rocky bed of ravine, course N.N.E., 75 lks. wide. Termination of 80 chs.</p> <p>Bearing:</p> <p>To out cropping rock on side of hill, a few links from bottom, N. 62°45'E., dist. 48 lks.</p> <p>To large "boulder" in bed of ravine, S. 7°46' W., dist. 3 chs.</p> <p>Made excavation; deposited a quantity of bones. Set cotton wood post, 8 ft. long & 7 ins. sq.; trimmed; top beveled; ground end charred. Built a monument of large rocks 8 ft. sq. & 4 ft. high. One of the most lasting monuments on Bdy. Could make no trench; placed 4 large boulders in place of pits. Marked post as all the others, except on W. side, "13 M." Passing along foot hill of mountain ridge; 9.90, intersected N. & S. line bet. Secs. 16-17, in lap of descending ridge.</p> <p>Bearings:</p> <p>To rock on side of mountain, S. 46°14' E., dist. 60 chs.</p> <p>To rock on side of mountain, S. 69°50' W.</p>
1/2 M.	
13 M.	
S 16-17	
1864 June 2	<p>Set post in mound; dug pits, trench, etc.; post a charred white thorn. Thence along foot hills of mountains; enter Walla Walla Valley, 40 chs. end. Foot of ridge, ascending to S.</p> <p>Bearings:</p>