

## Oregon and Washington Boundary Line.

	<p>Dug trench on 3 sides, the ditch is on the 4th or N. side. Dug pits, except on N. side.</p> <p>Bearings:</p> <p>Te Mr. Rice's chimney, S.45°28' E., dist. 1/3 mile.</p> <p>Mr. Goodman's chimney, N.33°30'E., dist. 10 chs.</p> <p>Mr. Mann's new house, N.53°34'W., dist. 2 1/3 miles.</p> <p>To rock projecting from ridge, S.70°57'W., dist. 4½ miles.</p> <p>E. over low flat bottom with some alkali patches, 70 chs., ascend bluff, 40 ft., thence along flat sandy plain, covered with sage brush, soil alkali. 80 chs. Made excavation, 3 ft. deep; deposited bones &amp; burnt stake.</p>
19 M.	<p>Planted cottonwood post, 8 ft. long, 8 ins. sq., beveled at top, marked on N. side "W", on S. "O", on E. "45° L 1864" &amp; on W. " 19 M".</p> <p>Bearings:</p> <p>To Mt. peak, N.78°26'E., dist.30 miles</p> <p>To Mt. peak, N.76°37'W., dist.15 miles</p> <p>To Golson's house,S.48°51'E., dist. 40 chs.</p> <p>To ridge of Rice's house, S.25°46'W.,dist. 25 chs.</p> <p>Built mound, 8 ft. sq. &amp; 4 ft. high; earth packed &amp; sodded.</p> <p>Dug deep rectangular trench &amp; 4 pits.</p> <p>A wagon road brs. N.W., dist. 15 lks., also another, S. 60 lks. Thence line passes through sparse sage brush and descends decline E. 6.50 chs. to intersection of Sec. line 16-17.</p>
S.16-17	<p>Bearings:</p> <p>To door of John Rich's house, S.76°20'E., dist. 60 chs.</p> <p>Timber on Mt. peak, S.78°22'E., dist. 25 miles.</p> <p>Rock on Mt. ridge, S.52°06'W., dist. 8 miles.</p> <p>Erected Sec. post of cottonwood, of proper size &amp; marking.</p> <p>Built mound; dug pits. The Bdy. passes into swampy edge of hollow, covered with brush to N., thence into enclosed claim of John Rich, 40 chs. end in swamp.</p>
1/2 M.	<p>Bearings:</p> <p>To high Mt. peak,Blue Mts., N.78°13'E., dist. about 30 miles.</p>