

## Oregon and Washington Boundary Line.

23 M	<p>Made excavation, 3½ ft. deep; deposited charred stake; planted cottonwood post, 9 ft. long &amp; 8 ins. sq., when sides trimmed &amp; top beveled. Marked as usual on N. face "W", on S. "O", on E. "46° L 1864" and on W. "23 M". Built earth mound, 8 ft. sq. at base and 4 ft. high, tapering to post. Sodded &amp; packed. Dug trench, pits, etc. 150 lbs. S. of post, a road hrs. N.E., thence up gentle swell of prairie 3.50 chs. to intersection of N. &amp; S. line bet. Rs. 34 &amp; 35 E., Sec. 13-18.</p>
S.13-18	<p>Bearings:</p> <p>To Catholic Seminary, Walla Walla, N.59°15'E., dist. 8½ miles.</p> <p>Center of far dist. Mt. peak, N.62°34'W., dist. 46 miles.</p> <p>Center of rock on side of Mt., S.20°38'W., dist. 5 miles.</p> <p>To lone pine on dist. Mt. side, S.22°19'E., dist. 15 miles.</p> <p>Deposited bones; planted post, marked T 6 N R 35 E S 18 and T 6 N R 34 E S 13; built mound; dug trench, pits, etc., thence E., the line passes along N. side of gentle hollow and over small hill and descending into shallow flat to the end of 40 chs.</p>
1/2 M.	<p>Bearings:</p> <p>To tree in Mt. Gap, S.68°22'E., dist. 24 miles.</p>
1864	<p>Made excavation; deposited bones; planted an alder post, 6 ft. long, &amp; 5 ins. diam.; marked on W. "1/2 M". Erected earth mound; dug trench &amp; pits. Passing over undulating prairie; descend to gravelly flat, seemingly the dry bed of an old river. The 80 chs. terminate on edge of small descent.</p>
June 11	<p>Bearings:</p> <p>To center of clump of pines on Blue Mts., N.63°43'E., dist., 20 miles.</p> <p>Chimney to house, S.68°24'E., dist. 1 mile.</p> <p>To mound, covered with brush, on side of Mt., S.46°29'W. dist. 7 M. Birch? tree on Mud Creek, dist. 1 M., N.48°48'W.</p> <p>Made excavation, 4 ft. deep. Deposited charcoal &amp; a large quantity of bones. Erected heavy alder post, 8 ft. long and 8 ins. sq., sides trimmed; top beveled and marked</p>
1/2 M.	