

## Oregon and Washington Boundary Line.

- 24 M. on N. face "W", on S. "O", on E. "46° L 1864" and on W. "24M". Built earth mound, 8 ft. sq. at base and 4 ft. high, tapering to top of post; earth packed & sodded.
- 17-18. Dug deep quadrangular trench & 4 pits. Sec. line 17-18, T 6 N R 35 E closes within limits and no post was erected; which is the case as far as the land surveys extend E. Proceeding E. along flat, 38.50 chs. to Mud Creek, a small, deep stream, 12 lks. wide, course N. & general direction W.N.W. Fringed with small brush and sides boggy. Land 1st & 2nd rate. 40 chs. end in angle of Mud Creek, 2 chs. N. of it. Mag. Var. 21°E.
- 1/2 M. Bearings:  
 To rock in ravine, S. 33°36'W., dist. 7 miles.  
 Gap in Mts., S. 66°51'E., dist. 22 miles.
- Made excavation, 3 ft. deep; deposited a quantity of charcoal. Planted birch post, 6 ft. long & 6 ins. sq., marked on W. face "1/2 M". Threw up earth mound; dug trench also pits, etc. E. across flat bottom 51 chs., ascend steep bluff, 50 ft. high, course N.W. Prominent land mark, 59 chs., cross wagon road, course SW., thence over hilly country, 80 chs. end on side of shallow flat, with decline to E.
- Bearings:  
 To timbered peak on Blue Mts., N. 75°46'E., dist. 25 miles.  
 Middle tree of three pines, close together on Mt. side, S. 26°54'E., dist. 18 miles. No other objects.
- 1864 June 13 Made excavation; deposited charcoal; erected cottonwood post, 8 ft. long & 8 ins. sq., top beveled, sides trimmed & marked on N. "W", on S. "O", on E. "46° L 1864" and on W. "25 M". Erected mound of earth, 8 ft. sq. at base and tapering 4 ft. high. Dug rectangular trench & 4 pits.
- 25 M From the 22nd to the 25th mile inc., the Bdy. was re-measured with a variation of 40 lks. except corresponding miles in the old section work of Tp. 7, do not accord well. E. the Bdy. line passes over sandy hills and alkalied flats to the end of the 40 chs.