

Oregon & Washington Boundary Line.

Bearings:

To Flag staff, Ft. Walla Walla, N.48°04'E., dist. 5½ miles.

To Yakima peak, N.77°38'W., dist. 50 miles.

Chimney on house, S.78°05'E., dist. 40 chs.

Bald spot, on rock, on Mt. side, S.51°13'W., dist. 8 miles.

Made excavation; deposited bones; planted post, 5½ ft. long,

1/2 M

4 ins. sq., marked on W. side "½ M." Built an earthen mound, well packed & sodded, 5 ft. at base & tapering 3 ft. high to post in center. Dug trench & 4 pits. 12 lks. E., wagon road, course N. by W. Proceeding 3 chs. E., edge of bluff & ditch, bearing N. by W. Enter enclosed claim of I. Beauchamp. Descend 40 ft. in ¼ chain. Thence through rich bottom, 46 chs. to Walla Walla tributary 30 lks. wide, running N., a clear rapid stream of good water, depth about 3 ft. Growth of brush and a few trees on banks. Soil; 1st rate. Land level bottom under cultivation. 70 chs. Beauchamp's house S. a few chains. 79.50 small tributary of last stream. 80 chs. end in cultivated field.

Bearings:

To Mt. peak with clump of timber on top, N.75°14'E., dist. 24 miles.

Rock on Mt. side, S.47°19'E., dist. 15 miles.

To small cottonwood tree, blazed & marked "O", S.22°W., dist. 2 chs. Diam. of tree 6 ins.

26 M.

Made excavation, 3½ ft. deep; deposited charcoal & charred

stakes. Planted post, alder, 8 ft. long & 8 ins. sq., durably marked on N. face "W", S. "O", E. "46 L 1864" and on W. "26 M". Built mound of earth; dug trench, also pits, all as usual. Thence through cultivated field, 24 chs., cross small stream, bearing N. Thence through enclosed claim of Mr. Harrington, 40 chs. terminate on small hill, N. & N.E.

1864

June 13

Bearings:

To John Dunn's house, S.10°27'E., dist. ½ mile.