

Oregon and Washington Boundary Line.

1/2 M. To Mr. Wm. Derrick's house, S. 5°23'W., dist.  
Birch tree, dist. 1/2 mile, N.77°02'W.  
Made excavation, 2 1/2 ft. deep; deposited bones; built mound  
4 ft. sq. & 3 ft. high; packed & sodded. Dug trench &  
4 pits. Post of birch, 5 1/2 ft. long & 4 ins. sq., marked  
on W. face "1/2 M". Land moderately level; soil, 2nd rate.  
E. through cultivated field, cross old wagon road, bearing  
enter  
N. & S., / stony flat, land worthless. 79 chs. cross wa-  
gon road, bearing S.W. 80 chs. end on W. edge of old  
wagon road, course N. & S.

Bearings:

27 M. To tree, N.21°50'E., dist. 2/3 mile.  
Chimney of M. Chartie's house, N.2°56'E., dist. 12 chs.  
Cottonwood tree, 12 ins. diam., blazed & marked "O",  
dist. 12 chs., S.42°37'E.  
Cottonwood tree, 12 ins. diam., blazed & marked "O", S.  
10°00'30"W.

Made excavation, and deposited charcoal. Planted cotton-  
wood post, 8 ft. long & 8 ins. sq. Marked as usual.  
Built mound; sodded; dug trench & pits, except on E.  
side, which was in road. Deposited bones. Bdy. passing  
E. in 4 chs. strikes the middle branch of Walla Walla  
River, 30 lks. wide, course N. by W., large volume of  
good water, current rapid. Sparse growth of cottonwood  
and alder on either bank. Thence through cultivated  
field of 1st class land to 17 chs., E. Fork of Walla  
Walla, 25 lks. wide, rapid current, good water & banks  
fringed with small timber & brush, course N. Thence  
through field cultivated by Mr. Egle, cross ditch and  
enter alkali flat, to end of 40 chs.

Bearings:

1/2 M. To highest Mt. peak ( no timber), N.79°05'E., dist. 20 miles  
Chimney to house, N.23°02'W., dist. 3/4 mile.  
Chimney, S.22°44'W., dist. 18 chs.  
Mountain Gap, S.61°50'E., dist. 22 miles.