

Oregon & Washington Boundary Line.

30 M.	<p>sq., trimmed, top beveled and marked on N. face "W", on S. "O", on E. "46° L 1864" and W. "30 M". Dug deep trench & 4 pits, like preceding mile mound.</p>
	<p>Bdy. passing E. in 90 lks., crosses County road, N. & S., thence over gently rolling country, 40 chs. terminate on slight inclination to S.</p> <p>Bearings:</p> <p>To house, N.60°09'E., dist. 1½ mile.</p> <p>Chimney to house, S.83°10'E., dist. 1 mile.</p> <p>Flag staff at Ft. Walla Walla, N.17°08'W., 4½ miles.</p>
1/2 M.	<p>Made excavation; deposited bones; planted a wild cherry post, 5½ ft. long & 4½ ins. wide, marked on W. face "½ M". Threw up earth mound; sodded; dug rectangular trench and 4 deep pits.</p>
1864 June 15	<p>Bdy. passes from this post up a shallow flat to higher level, soil & grass improving. Land rolling and of 2nd & 3rd rate. End of 80 chs., marked Bdy. as usual.</p>
31 M.	<p>Bearings:</p> <p>To large cottonwood tree on I. Dewars farm & Cottonwood Creek, N.44°31'E., dist. 1½ mile.</p> <p>Chimney to Capt. John Mallon's house, N.33°06'W., dist. 1½ miles.</p>
	<p>Chimney on house, S.74°55'E., dist. 50 chs.</p> <p>House on Walla Walla River, S.39°08'W., dist. 6 miles.</p> <p>Made excavation, 4 ft. deep; deposited bones; planted seasoned tamarack, 9½ ft. long & 10 ins. diam., trimmed, top beveled, and marked as preceding posts, except on W. side, "31M". Mound, 7 ft. sq. at base & 5 ft. high, Dug trench & pits as usual, E. in 2 chs. descend hill. 7.40 chs., Spring Creek, 6 lks. wide, no timber or brush, thence over gradual rise to 36.45 chs. Boise Road, brs. N. & S. 40 chs. end on edge of old road, course S.</p> <p>Bearings:</p> <p>To ridge of Simm's flour mill, N.34°53'W., dist. 2 miles, 55 chs.</p>