

Oregon & Washington Boundary Line.

1/2 M. timber, blazed & marked some pine trees near the Bdy. 12 chs., small opening on top of Mt., thence through pine & tamarack- 36 chs., cross wood road on top of ridge of Mt., course N. & S., thence through dense undergrowth and woods to 40 chs. Cut top of tamarack tree on line, left stump, 3 ft. high, properly marked, also blazed & marked "O", two trees, within a few feet of post and also one N. with the letter "W". Thence the Line passes through wooded top of Mt., the dividing ridge bet. Mill & Russell Creeks, Blazed many trees, along the Line. 60 chs., edge of descent to Mill Creek. Descending about 78 chs., Line crosses small ledge of rock, abutting from hill side. 79.50 to large pine, 5 lks. diam., close to Line, blazed & marked "W". Thence

40 M. to 80 chs. Built stone mound; marked stone slab on top "40 M 1864" 46°L."

Bearings:

To large pine, blazed & marked "W", N.86°E., dist. 2 chs.  
 To one of two dried firs, S.77°30'E., dist. 60 lks.,  
 blazed & marked "O", 2 ft. diam.  
 To pine tree, S.22°W., dist. 3 chs.  
 To pine, 2 ft. diam., N.48°W., dist. 65 lks.

Bdy. descends steep Mt. side to ravine, bearing N.E. Blazed two pines, 10 ins. diam., 50 lks. from Line, one N. with "W", the other S, "O". Cross ravine and ascend through very dense woods, of pine, fir & tamarack, blazing & marking two more large fir trees, 3 ft. diam. Planted post & erected 1/2 M. mound, in dense undergrowth & fallen timber. Blazed many trees close to Bdy. in this vicinity. The Bdy. leaving timber descends & crosses ravine, course E.S.E. Ascending along the side of steep rocky Mt. ridge, blazed & marked "O", three pines, just S. of Line and also three near top of ridge & N. of Line "W". Mile terminates at a lone Pine, on ridge, the tree is 24 ins. diam.

1/2 M.

41 M. and marked on E. "46° L 1864", on W. "41 M".

Bearings:

To N.E. Rock, N. 36°50'E., dist. 90 lks.