

Exteriors of T. 1 N., R. 29 E.
 Surveyed by David P. Thompson under contract No. 83.
 Dated July 22, 1859.

Chains	<p>I commenced at the estavlished corner to Townships 1, North of Ranges 28 and 29 East on the Base Line.</p> <p>North between secs. 31 and 36.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of stone.</p> <p>80.00 Set post for corner to secs. 30, 31, 25, and 36 in mound of Earth &c as per instructions.</p> <p>Land, rough and broken.</p> <p>Soil, 3rd rate.</p>
	<p>North between secs. 25 and 30.</p> <p style="text-align: center;">Var. 18° East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.</p> <p>65.70 Butter Creek, 20 lks. wide, runs N.W., bottom about 500 lks. wide.</p> <p>80.00 Set post for corner to secs. 24, 25, 19 and 30 in mound of Earth &c as per instructions.</p> <p>Land, rough and broken, stony.</p> <p>Soil, 3rd rate.</p>
	<p>North between secs. 19 and 24.</p> <p style="text-align: center;">Var. 18° 30' East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.</p> <p>80.00 Set post for corner to secs. 18, 19, 13 and 24 in mound of Earth &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good, 2nd rate.</p>
	<p>North between secs. 13 and 18.</p> <p style="text-align: center;">Var. 19° 30' East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.</p> <p>80.00 Set post for corner to secs. 12, 13, 7 and 18 in mound of Earth &c as per instructions.</p> <p>Land, gently rolling.</p>