

T. 1 N., R. 29 E.

Chains 40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.	
80.00	Set post for corner to secs. 5, 6, 31 and 32 in mound of Earth &c as per instructions. Land, gently rolling. Soil, good, 2nd rate.	
	S. 89° 39' W., on true line between secs. 6 and 31. Var. 21 $\frac{3}{4}$ ° East.	
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.	
86.00	The corner to Townships 1 and 2, North of Ranges 28 and 29 East. Var. 20° East. Land, gently rolling. Soil, good, 2nd rate. August 23, 1859.	
	General Description	
	The quality of Land in this Township is good, 2nd rate, high rolling Prairie covered with Bunch Grass and will admit of some settlement and should be subdivided.	
	Resurvey of the East boundary of T. 1 N, R. 28 E. Surveyed by L.F. Cartee under Contract No. 88. Dated May 11, 1860.	
	Having detected an error of 5 chains in the length of the East boundary of sec. 36, I commence at the established corner on the Base Line and run as follows: North on the line between secs. 31 and 36.	
0.00	Descend hill E. and W.	-200
12.00	Ascend hill slopes S.	
40.00	Set post for qr. sec. cor. and built mound of stone as per instructions.	
65.00	Top of ridge, course N.W. and S.E.	-100
80.00	Set post for corner to sections 25, 30, 31 and 36	