

Subdivisions of T. 1 N., R. 29 East.

Chains	
79.44	Intersect line 25 lks. North of sec. cor. N. 89° 49' W., on true line, between secs. 13 and 24.
39.72	Set post for qr. sec. cor. and built mound of Earth as per instructions.
79.44	To section corner. Land, rolling. Soil, 2nd rate.
	North between sections 13 and 14.
40.00	Set post for qr. sec. corner and built mound of Earth as per instructions.
80.00	Set post for corner to sections 11, 12, 13 and 14, and built mound of Earth as per instructions. Land, rolling. Soil, 2nd rate.
	East, on random line, between sections 12 and 13. Var. 19° 45' East.
40.00	Set temp. qr. sec. posts.
79.30	Intersect line, 25 lks. North of corner. N. 89° 49' W., on true line, between secs. 12 and 13.
39.65	Set post for qr. section corner and built mound of Earth as per instructions.
79.30	To sections corner. Land, rolling. Soil, 2nd rate.
	North between sections 11 and 12.
40.00	Set post for qr. sec. corner and built mound of stone as per instructions.
80.00	Set post for corner to sections 1, 2, 11 and 12 and built mound of stone as per instructions. Land, rolling. Soil, 3rd and 2nd rate.
	East, on random line, between secs. 1 and 12.