

Subdivisions of T. 1 N., R. 29 E.

Chains	
	Var. 20° 30' East.
40.00	Set temp. qr. sec. post.
78.35	Intersect line, 25 lks. N. of corner. N. 89° 49' W., on true line, between secs. 1 and 12.
39.17	Set post for qr. sec. corner and built mound of Earth as per instructions.
78.35	To section corner. Land, broken. Soil, 3rd rate and stony.
	May 14, 1860
	North between sections 1 and 2 on random.
40.00	Set temp. qr. sec. post.
79.40	Intersect line 86 lks. East of post. S. 37' E., on true line between sections 1 and 2.
39.40	Set post for qr. sec. cor. and built mound of Earth as per instructions.
79.40	To section corner. Land, gently sloping North. Soil, 2nd rate.
	North on line between sections 34 and 35.
40.00	Set qr. section corner and built mound of stone as per instructions.
80.00	Set post for corner to sec. 26, 27, 34 and 35 and built mound of Earth as per instructions. Land, on first $\frac{1}{2}$ mile broken and stony. 2nd slopes North. Soil, 3rd and 2nd rate.
	East, on random line, between secs. 26 and 35. Var. 19° 45' East.
40.00	Set temp. qr. section post.
79.70	Intersect line, 40 lks. South of corner. S. 89° 43' W., on true line between secs. 26 and 35.
39.85	Set post for qr. sec. corner and built mound of Earth as per instructions.

+100