

T. 1 N., R. 30 E.

Chains	
	<p>North between secs. 7 and 12.</p> <p style="text-align: center;">Var. 16° 15' East.</p>
35.00	<p>Trail from Umatilla River to Butter Creek bears N. 15° W. S. 15° E.</p>
40.00	<p>Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.</p> <p style="text-align: center;">Var. 18° 45' East.</p>
80.00	<p>Set post for corner to secs. 6, 7, 1 and 12 in mound of Earth &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good, 2nd rate.</p>
	<p>North between secs. 1 and 6.</p> <p style="text-align: center;">Var. 20° East.</p>
40.00	<p>Set post for $\frac{1}{4}$ sec. corner in mound of Earth and stone &c as per instructions.</p>
80.00	<p>Set post for corner to Townships 1 and 2 North of Ranges 29 and 30 East, in mound of stone &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good, 2nd rate.</p>
	<p>From the corner to Townships 1 and 2 N. of Ranges 29 and 30 East. I run. East on a random line between said Townships and set temporary half mile and mile posts at 40.00 and 80.00 chains. I find the Township line to be 6 miles, 5 chains and 40 links and the falling to be 80 links South of the Township corner. The length of the line being too long I rechaind it and reran the North and West boundary and found no error. I then rechaind the South boundary on the Base Line and find it to be 6 miles, 6 chains and 8 links in length.</p>
	<p>From the established corner to Townships 1 and 2 North of Ranges 30 and 31 East. I run. S. 89° 54' W., on true line, between secs. 1 and 36.</p>