

Remeasurement of Base Line through 30 East.

Chains	Land, nearly level prairie. Soil, good, 2nd rate.
	West on South boundary of sec. 32. Var. $19\frac{1}{4}^{\circ}$ East.
40.00	Set qr. sec. post. Drove charred stake and built mound with trench and pits as per instructions. Destroyed pre-established qr. sec. cor.
80.00	Set post for cor. to secs. 31 and 32. Drove charred stake and built mound with trench and pits as per instructions. Destroyed pre-established sec. cor. Land, nearly level prairie. Soil, good, 2nd rate.
	West on South boundary of sec. 31. Var. $21^{\circ} 30'$ East.
16.50	An Indian trail, course N. and S.
40.00	Set qr. sec. post. Drove charred stake and built mound with trench and pits as per instructions. Destroyed pre-established qr. sec. cor.
87.67	The corner to Townships No. 1 North, Ranges 29 and 30 East Will. Mer. Land and soil same as last mile. October 29, 1860.
	Subdivisions of T. 1 N., R. 30 E. Surveyed by Wm. B. Campbell under contract No. 95. Dated September 19, 1860.
	North between secs. 35 and 36. Var. $21^{\circ} 15'$ E.
40.00	Set post for quarter sec. cor. in mound of stone on southern slope of ridge and ascend level.
80.00	Set post for corner to secs. 25, 26, 35 and 36 and raised †50