

## Subdivisions of T. 1 N., R. 30 E.

Chains 80.00	Set post for corner to secs. 11, 12, 13 and 14 and raised mound of earth and drove charred stake with trench and pits as per instructions.  Land, rolling prairie.  Soil, good, 2nd rate.	-60
	East on random line between secs. 12 and 13.  Var. $18\frac{1}{2}^{\circ}$ E.	
40.00	Set temporary quarter sec. post and descend.	
80.72	Intersect Guide Meridian, 30 lks. S. of corner to secs. 7, 12, 13, and 18.  S. $89^{\circ} 47'$ W., on true line, between secs. 12 and 13.	
37.48	Top of ascent and descend.	
40.36	Set quarter section post and raised mound of earth and drove charred stake with trench and pits as per instructions. Descend from qr. post.	+50
80.72	The post corner to secs. 11, 12, 13 and 14.  Land, rolling prairie.  Soil, good, 2nd rate.	
	North between secs. 11 and 12.  Commence descent gradually.	
40.00	Set quarter sec. post, drove charred stake and raised mound of earth with trench and pits as per instructions, and ascend from post.	-40
80.00	Set post for corner to secs. 1, 2, 11 and 12. Drove charred stake, raised mound of earth with trench and pits as per instructions.  Land, rolling prairie.  Soil, good, 2nd rate.	+50
	East on random line between secs. 1 and 12.  Var. $19\frac{1}{2}^{\circ}$ E.	
40.00	Set temporary quarter sec. post.	+30
80.42	Intersect Guide Meridian 42 lks. South of corner to secs. 1, 6, 7 and 12.	