

## Subdivisions of T. 1 N., R. 30 E.

Chains		
58.50	To foot of descent and big hollow.	-200
64.25	Cross same and ascend.	
67.75	Rocks cropping out.	
80.00	Set post on Western slope near the top; drove charred stake in mound &c.	+200
	Land, very much broken in this vicinity.	
	Soil, 2nd and 3rd rate.	
East on random line between secs. 14 and 23.		
Var. 22° E.		
40.00	Set temp. quarter sec. post.	
80.30	Intersect N. and S. line, 40 lks. South of corner to secs. 13, 14, 23 and 24.	
	S. 89° 43' W., on true line, between secs. 14 and 23.	
28.30	Commence descent.	
40.15	Set quarter section post, drove charred stake and raised mound as per instructions.	
51.30	To foot of descent and ascend.	-60
65.30	To top of ascent.	+50
80.30	The corner to secs. 14, 15, 22 and 23.	
	Land, rolling prairie.	
	Soil, 2nd and 3rd rate.	
North between secs. 14 and 15.		
Commence to ascend from post.		
22.50	To top of ascent and descend.	+50
40.00	Set quarter sec. post, drove charred stake and raised mound of Earth as per instructions.	
80.00	Set post for corner to secs. 10, 11, 14 and 15. Drove charred stake, raised mound of earth with trench and pits as per instructions.	-25
	Land, stony 1st $\frac{1}{2}$ mile, balance good, 2nd rate.	
East on random line between secs. 11 and 14.		
Var. 21° 15.		