

Subdivisions of T. 1 N., R. 30 E.

Chains			
40.00	Set temporary quarter sec. post.		Level
80.00	Intersect N. and S. line, 10 lks. South of corner to secs. 11, 12, 13 and 14. S. 89° 56' W., on true line, between secs. 11 and 14. Commence ascent.		-50
15.00	To top of ascent and descend.		+50
40.00	Set quarter sec. post, drove charred stake and raised mound of earth as per instructions.		Level
53.75	To foot of descent.		-25
75.00	Ascend to post.		
80.00	The post corner to secs. 10, 11, 14 and 15. Land, rolling prairie. Soil, good, 2nd rate.		+40
North between secs. 10 and 11.			
40.00	Set post for quarter sec. corner, drove charred stake and raised mound of Earth with trench and pits as per instructions.		
80.00	Set post for corner to secs. 2, 3, 10 and 11. Drove charred stake, raised mound of Earth with trench and pits as per instructions. Land, gently rolling prairie. Soil, good, 2nd rate.		
October 21, 1860			
East on random line between secs. 2 and 11. Var. 19° E.			
40.00	Set temporary quarter sec. post on bluff.		+40
80.02	Intersect N. and S. line, 16 lks. South of corner to secs. 1, 2, 11 and 12. S. 89° 53' W., on true line between secs. 2 and 11. Commence descent from post.		
37.52	Ledge of basaltic rock cropping out and scattered around.		
40.01	Set post for quarter sec. corner in rock mound as per instructions.		-40
46.00	To foot of rocky bluff and ascend gradually.		-80