

## Subdivisions of T. 1 N., R. 30 E.

Chains 80.02	The post corner to secs. 2 , 3, 10 and 11. Land, on bluff poor, 3rd rate, balance good 2nd rate.	
	North on random line between secs. 2 and 3.	
40.00	Set temporary quarter sec. post.	
82.46	Intersect North boundary of Township , 70 lks. East of post corner to secs. 3 and 2. S. 00° 30' E. on true line between secs. 2 and 3.	Level
42.46	Set post for quarter sec. corner, drove charred stake and raised mound of earth with trench pits as per instructions; rolling and ascending.	
49.96	To top of ascent and descend.	+50
80.46	To Ravine, course N.E. and S.W.	
82.46	The post corner to secs. 2, 3, 10 and 11. Land, rolling prairie. Soil, good, 2nd rate.	
	North between secs. 33 and 34.	
40.00	Set a post for quarter section corner, drove charred stake and raised mound of earth with trench and pits as per instructions.	Level
80.00	Set post for corner to secs. 27, 28, 33 and 34. Drove charred stake and raised mound of earth with trench and pits as per instructions. Land, smooth prairie nearly level. Soil, good, 2nd rate.	-25
	East on random line between secs. 27 and 34. Var. 21° E.	
40.00	Set temporary quarter section post.	+20
80.02	Intersect corner to secs. 26, 27, 34 and 35 at post. West on true line between secs. 27 and 34.	-25
40.01	Set a post for quarter section corner, drove charred stake and raised mound of earth with trench and pits as per instructions.	+25
80.02	The corner to secs. 33, 34, 27 and 28.	-20