

## Subdivisions of T. 1 N., R. 30 E.

Chains		
	Land, rolling prairie. Soil, good, 2nd rate.	
	North between secs. 27 and 28.	
40.00	Set a post for quarter section corner, drove charred stake and raised mound of earth with trench pits as per instructions, on northern slope.	Level
80.00	Set a post for corner to secs. 21, 22, 27 and 28. Drove charred stake, built mound of earth &c as per instruction. Land and Soil same as above.	
	East on random line between secs. 22 and 27. Var. 21° 15' E.	
40.00	Set temporary quarter sec. post on top of a ridge descending North.	+50
80.20	Intersect corner to secs. 22, 23, 26 and 27 at post. West on true line between secs. 22 and 27.	Level
40.10	Set post for quarter sec. corner on top of a ridge descending North, drove charred stake and raised mound of earth with trench and pits as per instructions and descend.	
62.20	To foot of descent and ascend.	-50
77.20	To top of ascent.	+50
80.20	The post corner to secs. 22, 23, 27 and 28. Land, considerably rolling. Soil, good, 2nd rate.	
	North between secs. 21 and 22.	
40.00	Set post for quarter sec. corner on gentle slope to the North, drove charred stake and raised mound of earth with trench and pits as per instructions.	
80.00	Set post for corner to secs. 15, 16, 21 and 22 on Northern slope towards big hollow. Drove a charred stake and built mound of earth with trench and pits as per instructions. Land, rolling prairie.	