

Subdivisions of T. 1 N., R. 30 E.

Chains		
79.78	Intersect N. and S. line, 11 lks. South of post corner to secs. 15, 16, 21 and 22.	
	S. 89° 35' W. on true line between secs. 16 and 21.	
20.78	To hollow and ascend.	200
39.89	Set a post for quarter sec. corner, drove charred stake and raised mound of earth as per instructions.	100
58.78	To hollow and ascend.	
79.78	The corner to secs. 16, 17, 20 and 21.	
	Land, very rolling.	
	Soil, 2nd rate.	
	North between secs. 16 and 17.	
	Commence descent from post.	
40.00	Set a post for quarter sec. corner, drove charred stake and raised mound of earth &c as per instructions.	150
41.50	To foot of hill and ascend very steep rocky bluff, course of hollow N.W. and S.E.	
44.45	To perpendicular rocks.	25
55.00	To top of bluff.	200
66.00	Commence descending bluff.	
80.00	Set a post for corner to secs. 8, 9, 16 and 17 near foot of bluff and big hollow. Drove a charred stake and raised mound with trench and pits as per instructions.	
	Land, on bluff rocky 3rd rate, balance good 2nd rate.	
	East on random line between secs. 9 and 16.	
	Var. 20° 00' E.	
40.00	Set temporary quarter sec. post.	75
79.96	Intersect post corner to secs. 9, 10, 15 and 16.	
	West on true line between secs. 9 and 16.	
9.96	Commence descending.	
39.98	Set a post for quarter sec. corner, drove charred stake and raised mound of earth as per instructions.	75
71.96	To foot of descent.	150
79.96	The post corner to secs. 8, 9, 16 and 17.	
	Land, very rolling.	