

Subdivisions of T. 1 N., R. 30 E.

| Chains | | |
|---------------------|---|-------|
| | Land, rolling. Soil, 2nd rate. | |
| | North between secs. 31 and 32. Commence gentle descent. | |
| 40.00 | Set a post for quarter sec. corner, drove charred stake and raised mound of earth as per instructions. | -40 |
| 66.00 | To foot of descent and ascent. | -60 |
| 80.00 | Set a post for corner to secs. 29, 30, 31 and 32. Drove a charred stake and raised mound of earth with trench and pits as per instructions. | +20 |
| | Land, rolling prairie. Soil, good, 2nd rate. | |
| | East on random line between secs. 29 and 32. Var. 20° E. | |
| 40.00 | Set temporary quarter sec. post. | +50 |
| 80.29 | Intersect corner to secs. 28, 29, 32 and 33 at post. West on a true line between secs. 29 and 32. | Level |
| 40.14 $\frac{1}{2}$ | Set a post for quarter sec. corner, drove charred stake and raised mound of earth with trench and pits as per instructions. | Level |
| 80.29 | The corner to secs. 29, 30, 31 and 32. Land, rolling prairie. Soil, good, 2nd rate. | -50 |
| | West on random line between secs. 30 and 31. Var. 20° 00' E. | |
| 40.00 | Set temporary quarter sec. post. | -50 |
| 87.67 | Intersect West boundary of Township at post, corner to secs. 30 and 31. | +80 |
| | East on true line between secs. 30 and 31. Commence descent. | |
| 7.00 | Indian Trail N. and S. | |
| 28.67 | To foot of descent. | -80 |
| 35.17 | Cross bottom and ascend. | |