

Subdivisions of T. 1 N., R. 31 E.

Chains	
	North between secs. 25 and 26.
40.00	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound as per instructions.
80.00	Set a post for corner to secs. 23, 24, 25 and 26, drove charred stake and raised mound as per instructions.
	Land, rolling grass hills.
	Soil, 2nd rate.
	East on random line between secs. 24 and 25.
	Var. 20° 30' E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.50	Intersected East boundary of Township, 33 lks. South of the corner to secs. 24 and 25 from which corner I run.
	S. 89° 46' W., on a true line between secs. 24 and 25.
39.75	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
79.50	The corner to secs. 23, 24, 25 and 26.
	Land, level.
	Soil, 2nd rate.
	North between secs. 23 and 24.
40.00	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
70.00	To bed of dry Ravine, course N. 30° E.
80.00	Set a post for corner to secs. 13, 14, 23 and 24, drove charred stake and raised mound with trench as per instructions.
	Land, rolling grass hills.
	Soil, 2nd rate.
	East on a random line between secs. 13 and 24.
	Var. 18° 00' E.
40.00	Set a temporary $\frac{1}{4}$ sec. cor.
79.65	Intersected East boundary of Township at the post corner of secs. 13 and 14, from which I run.
	West on true line between secs. 13 and 24.