

## Subdivisions of T. 1 N., R. 31 E.

Chains	<p>the corner to secs. 2 and 3, from which corner I run. S. 0° 20' E. on true line between secs. 2 and 3.</p> <p>41.84 Set a post for <math>\frac{1}{4}</math> sec. cor., drove charred stake and raised mound with trench as per instructions.</p> <p>70.34 To a dry ravine, course N. 70° E.</p> <p>81.84 The corner to secs. 2, 3, 10 and 11. Land, rolling grass hills. Soil, 3rd rate.</p> <p style="text-align: right;">October 19, 1860.</p>
	<p>North between secs. 33 and 34.</p> <p>40.00 Set post for <math>\frac{1}{4}</math> sec. cor., drove charred stake and raised mound with trench as per instructions.</p> <p>80.00 Set post for corner to secs. 27, 28, 33 and 34, drove charred stake and raised mound with trench as per instructions. Land, rolling grass hills. Soil, 2nd rate.</p>
	<p>East on a random line between secs. 27 and 34. Var. 19° 00' E.</p> <p>40.00 Set temporary <math>\frac{1}{4}</math> sec. cor.</p> <p>80.08 Intersected N. and S. line, 58 lks. North of the corner to secs. 26, 27, 34 and 35, from which corner I run. N. 89° 35' W. on a true line between secs. 27 and 34.</p> <p>36.00 To a dry ravine, course N.E.</p> <p>40.04 Set post for <math>\frac{1}{4}</math> sec. cor., drove charred stake and raised mound with trench as per instructions.</p> <p>80.08 The corner to secs. 27, 28, 33 and 34. Land, rolling grass hills. Soil, light 2nd rate.</p>
	<p>North between secs. 27 and 28.</p> <p>25.00 Top of ridge, course N.E. and S.W.</p> <p>40.00 Set a post for <math>\frac{1}{4}</math> sec. cor., drove charred stake and raised mound with trench as per instructions.</p>