

Subdivisions of T. 1 N., R. 31 E.

Chains	North between secs. 29 and 30.
40.00	Set a post for $\frac{1}{4}$ sec. cor., and raised stone mound as per instructions.
80.00	Set a post for cor. to secs. 19, 20, 29 and 30, and raised stone mound as per instructions. Land, gently rolling. Soil, 2nd rate.
	East on random line between secs. 20 and 29. Var. 20° 00' E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.70	Intersect N. and S. line at post cor. to secs. 20, 21, 29 and 28, from which corner I run. West on true line between secs. 20 and 29.
39.85	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
79.70	The corner to secs. 19, 20, 29 and 30. Land, gradually rolling. Soil, 2nd rate.
	West on random line between secs. 19 and 30.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
89.40	Intersect West boundary of Township, 95 lks. South of the corner to secs. 19 and 30, from which corner I run. S. 89° 19' E. on true line between secs. 19 and 30.
49.40	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
50.00	To a dry ravine, course N. and S.W.
89.40	The corner to secs. 19, 20, 29 and 30. Land, stony.
	North between secs. 19 and 20.
40.00	Set post for $\frac{1}{4}$ sec. cor. and drove charred stake and raised stone mound with trench as per instructions.
80.00	Set post for corner to secs. 17, 18, 19 and 20, drove charred stake and raised mound with trench as per