

Subdivisions of T. 1 N., R. 31 E.

Chains	
	<p>instructions.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p>
	<p>East on random line between secs. 17 and 20.</p> <p style="text-align: center;">Var. 20° 00' E.</p>
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.80	Intersected N. and S. line, 30 lks. North of the corner to secs. 16, 17, 20 and 21, from which corner I run. N. 89° 47' W. on true line between secs. 17 and 20.
39.90	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
79.80	The corner to secs. 17, 18, 19 and 20.
	Land, broken.
	Soil, 2nd and 3rd rate.
	October 23, 1860.
	West on a random line between secs. 18 and 19.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
89.48	Intersected West boundary of Township, 148 lks. South of corner to secs. 18 and 19, from which corner I run. S. 88° 57' E. on a true line between secs. 18 and 19.
49.48	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
55.00	To a dry ravine, course N. and S.
89.48	The corner to secs. 17, 18, 19 and 20.
	Land, rolling.
	Soil, 2nd and 3rd rate.
	North between secs. 17 and 18.
40.00	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.00	Set a post for corner to sec. 7, 8, 17 and 18, drove charred stake and raised mound with trench as per instructions.