

Subdivisions of T. 1 N., R. 31 E.

Chains	
	Land, level. Soil, good, 2nd rate.
	East on random line between secs. 8 and 17. Var. 20° 00' E.
40.00	Set a temporary $\frac{1}{4}$ sec. cor.
79.70	Intersected N. and S. line, 40 lks. North of the corner to secs. 8, 9, 16 and 17, from which I run. N. 89° 43' W. on a true line between secs. 8 and 17.
39.85	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
75.00	To a dry ravine, course North.
79.70	The corner to secs. 7, 8, 17 and 18. Land, rolling. Soil, 2nd and 3rd rate.
	West on a random line between secs. 7 and 18.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
89.50	Intersected West boundary of Township, 200 lks. South of the corner to secs. 7 and 18, from which corner I run. S. 88° 34' E. on a true line between secs. 7 and 18.
49.50	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
89.50	The corner to secs. 7, 8, 17 and 18. Land, rolling. Soil, 2nd rate.
	North between secs. 7 and 8.
20.00	A dry ravine, course East.
40.00	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.00	Set a post for corner to secs. 5, 6, 7 and 8, drove charred stake and raised mound with trench as per instructions. Land, broken and stony.