

Subdivisions of T. 1 N., R. 31 E.

Chains	East on random line between secs. 5 and 8. Var. 21° 00' E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.22	Intersected N. and S. line, 44 lks. North of the corner to secs. 4, 5, 8 and 9, from which corner I run. N. 89° 41' W. on a true line between secs. 5 and 8.
39.61	Set post for $\frac{1}{4}$ sec. cor. and drove charred stake and raised mound with trench as per instructions.
79.22	The corner to secs. 5, 6, 7 and 8. Land, broken and stony.
	West on a random line between secs. 6 and 7.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
89.75	Intersected West boundary of the Township, 268 lks. South of the corner to secs. 6 and 7, from which corner I run. S. 88° 57' E. on a true line between secs. 6 and 7.
49.75	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
89.75	The corner to secs. 5, 6, 7 and 8. Land, rolling. Soil, 2nd and 3rd rate.
	North on random line between secs. 5 and 6.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
83.00	Intersected North boundary of the Township, 52 lks. East of the corner to secs. 5 and 6, from which corner I run. S. 0° 22' E. on a true line between secs. 5 and 6.
43.00	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
83.00	The corner to secs. 5, 6, 7 and 8. Land, South half level 2nd rate soil, North half broken and stony.
	October 24th, 1860.
	General Description
	The quality of the land in this Township is about an