

Exterior Boundaries of T. 1 N., R. 32 E.

Chains	
	obliterate.
80.00	Set stone, 15 x 10 x 10 ins., for corner to secs. 34 and 35. Land, rolling. Soil, 1st rate.
<hr/>	
	West on South boundary of sec. 34. Var. 19° 50' East.
2.80	Old corner to secs. 34 and 35.
40.00	Set stone, 16 x 15 x 8 ins., for $\frac{1}{4}$ sec. corner.
74.40	Road bears N. and S.
76.00	Enter Field bears N. and S.
80.00	Set post for corner to secs. 33 and 34 in mound of earth with charred stake, pits, trench &c as per instructions. Land, gently rolling. Soil, 1st rate.
<hr/>	
	West on South boundary of sec. 33. Var. 20° 45' East.
20.80	Leave Field bears N. and S.
22.75	Birch Creek dry, bears North.
40.00	Set stone 17 x 12 x 8 ins., for $\frac{1}{4}$ sec. corner.
44.90	Old established $\frac{1}{4}$ sec. corner.
80.00	Set post for corner to secs. 32 and 33 in mound of earth with charred stake, pits, trench &c as per instructions. Land, rolling. Soil, 1st rate. Some cotton wood and birch timber on creek banks.
<hr/>	
X	West on South boundary of sec. 32. Var. 19° 45' East.
5.60	Old established corner to secs. 32 and 33.
40.00	Set stone 18 x 12 x 4 ins., for $\frac{1}{4}$ sec. corner.
46.30	Old established $\frac{1}{4}$ sec. corner.
80.00	Set post for corner to secs. 31 and 32 in mound of earth with charred stake, pits, trench &c as per instructions.