

Exterior Boundaries of T. 1 N., R. 32 E

Chains	Enter Field.	
40.00	Set post for $\frac{1}{4}$ sec. corner from which A balm, 5 ins. diam., bears S. 17° E. 79 lks. dist. " " 15 " " " N. 87° W. 100 " "	
46.82	Leave Field, course N. and S.; ascend hill.	
65.00	Top of hill bears N and S.	+250
79.40	Road bears N. and S.	
80.00	Set post for corner to secs. 3, 4, 33 and 34 in mound of earth with charred stake, pits, trench &c as per instructions. Land, rolling. Soil, 1st rate.	
	S. 89° 55' East on North boundary of sec. 3. Var. 19° 30' East.	
40.00	Set post for $\frac{1}{4}$ sec. corner.	
64.00	Dry bed of creek, course N.W.	
80.00	Set stone, 24 x 15 x 10 ins., for corner to secs. 2, 3, 34 and 35. Land, rolling. Soil, 1st rate. Some balm timber on dry creek.	
	S. 89° 55' E. on North boundary of sec. 2. Var. 19° 30' East.	
11.25	Road bears N.E. and S.W.	
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.	
80.00	Set post for corner to secs. 1, 2, 35 and 36 in mound of earth with charred stake, pits, trench &c as per instructions. Land, gently rolling. Soil, good, 2nd rate. Fine grass.	
	S. 89° 55' East on North boundary of sec. 1.	