

## Subdivisions of T. 1 N., R. 32 E.

Chains	East on a random line between secs. 26 and 35.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect N. and S. line at corner to secs. 25, 26, 35 and 36 from which I run.
	West on a true line between secs. 26 and 35.
22.78	Brook, 6 lks. wide, runs N. 20° W.
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions
80.00	The corner to secs. 26, 27, 34 and 35. Land, gently rolling. Soil, 1st rate.
	North between secs. 26 and 27. Var. 19 $\frac{3}{4}$ ° E.
36.50	Road bears N.E. and S.W.
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to secs. 22, 23, 26 and 27 in mound of earth with charred stake, pits as per instructions. Land, level. Soil, 1st rate. October 20th, 1864.
	East on a random line between secs. 23 and 26.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect N. and S. line at corner to secs. 23, 24, 25 and 26 from which I run.
	West on a true line between secs. 23 and 26.
28.00	Dry bed of creek bears N.W.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
46.50	Road bears N.E. and S.W.
80.00	The corner to secs. 22, 23, 26 and 27. Land, gently rolling. Soil, 1st rate.