

Subdivisions of T. 1 N., R. 32 E.

Chains	North between secs. 22 and 23. Var. 19 3/4° E.
35.50	Road bears N.E. and S.W.
40.00	Set post for 1/4 sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to secs. 14, 15, 22 and 23 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 1st rate.
	East on a random line between secs. 14 and 23.
40.00	Set temporary 1/4 sec. corner.
80.00	Intersect N. and S. line at corner to secs. 13, 14, 23 and 24 from which I run. West on a true line between secs. 14 and 23.
32.75	Dry bed of creek, course N.W.
34.40	Road bears N. and S.
40.00	Set post for 1/4 sec. corner in mound of earth with charred stake, pits &c as per instructions.
73.60	Road bears N.E. and S.W.
80.00	The corner to secs. 14, 15, 22 and 23. Land, gently rolling. Soil, 1st rate.
	North between secs. 14 and 15. Var. 20° E.
13.00	Road bears N.E. and S.W.
40.00	Set post for 1/4 sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to secs. 10, 11, 14 and 15 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 1st rate.
	East on a random line between secs. 11 and 14.
40.00	Set post for temporary 1/4 sec. corner.