

## Subdivisions of T. 1 N., R. 32 E.

Chains	
80.40	Intersect North boundary at corner to secs. 2 and 3 from which corner I run. South on true line between secs. 2 and 3.
17.50	Dry bed of creek runs N.W.
24.00	Same creek runs N.E.
30.00	Same creek runs N.W.
40.40	Set post for $\frac{1}{4}$ sec. corner from which A cotton wood, 10 ins. diam., bears N.75°W.34 lks. dist. " " " 18 " " " N.15°E.96 " "
80.40	The corner to secs. 2, 3, 10 and 11. Land, level creek bottom. Soil, 1st rate. Timber, cotton wood.
	North between secs. 33 and 34.
12.50	Spring brook, 3 lks. wide, runs N.E.
22.50	Birch creek (dry bed) course N.E.
24.80	Leave field, bears N.E. and S.W.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to secs. 33, 34, 27 and 28 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 1st rate. Timber, cotton wood and birch.
	East on a random line between secs. 27 and 34.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
80.30	Intersect N. and S. line at corner to secs. 26, 27, 34 and 35 from which I run. West on a true line between secs. 27 and 34.
26.55	Road bears N and S.
33.00	Birch creek, 6 lks. wide runs N.E.
40.15	Set stone, 15 x 8 x 8, for $\frac{1}{4}$ sec. corner.
80.30	The corner to secs. 27, 28, 33 and 34. Land, rolling.