

## Subdivisions of T. 1 N., R. 32 E.

Chains	
	<p>Soil, 1st rate.</p> <p>Some cottonwood and birch timber on the creek.</p>
	<p>North between secs. 27 and 28.</p> <p style="text-align: center;">Var. 20° E.</p>
40.00	Set stone, 15 x 8 x 5, for $\frac{1}{4}$ sec. cor.
80.00	Set post for corner to secs. 21, 22, 27 and 28 in mound of earth with charred stake, pits &c as per instructions.
	<p>Land, rolling.</p> <p>Soil, 1st rate.</p>
	<p>East on a random line between secs. 22 and 27.</p>
40.00	Set post for temporary $\frac{1}{2}$ sec. cor.
80.30	Intersect N. and S. line, 70 lks. North of corner to secs. 22, 23, 26 and 27 from which corner I run.
	N. 89° 30' W. on a true line between secs. 22 and 27.
22.80	Road bears N and S.
26.10	Enter field, bears N and S.
38.25	Birch creek, 10 lks. wide, runs North.
40.15	Set post for $\frac{1}{4}$ sec. corner from which
	A birch, 10 ins. diam., bears S. 60° E. 7 lks. dist.
	A yellow wood 4 ins. diam. bears N. 45° W. 8 lks. dist.
80.30	The corner to secs. 21, 22, 27 and 28.
	<p>Land, gently rolling.</p> <p>Soil, 1st rate.</p> <p>Timber on creek, cotton wood and birch.</p>
	<p>North between secs. 21 and 22.</p> <p style="text-align: center;">Var. 22° E.</p>
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to secs. 15, 16, 21 and 22 in mound of earth with charred stake, pits &c as per instructions.
	<p>Land, gently rolling.</p> <p>Soil, 1st rate.</p>