

Subdivisions of T. 1 N., R. 32 E.

Chains	
	Land, rolling. Soil, 1st rate. Cotton wood timber on creek.
	North between secs. 9 and 10. Var. $19\frac{1}{2}^{\circ}$ E.
8.00	Road bears N.W. and S.E.
40.00	Set post for $\frac{1}{4}$ sec. cor. from which A balm, 14 ins. diam. bears S. 70° E. 25 lks. dist. " " 14 " " " S. 4° W. 115 " "
45.00	Birch Creek, 8 lks. wide, runs N.W.
80.00	Set post for corner to secs. 3, 4, 9 and 10 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 1st rate.
	East on a random line between secs. 3 and 10.
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.
79.80	Intersect N. and S. line, 70 lks. North of corner to secs. 2, 3, 10 and 11 from which I run. N. $89^{\circ} 30'$ W. on a true line between secs. 3 and 10.
39.90	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
45.00	Road bears N.E. and S.W. Descend hill.
79.80	The corner to secs. 3, 4, 9 and 10. Land, hilly. Soil, good, 2nd rate.
	North on a random line between secs. 3 and 4. Var. $19^{\circ} 30'$ E.
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.
80.00	Intersect North boundary at corner to secs. 3 and 4 from which I run. South between secs. 3 and 4 on true line.
.75	Road bears N.W. and S.E.
32.50	Road bears E. and W.