

Subdivisions of T. 1 N., R. 32 E.

Chains	
	<p>2nd rate, level or gently rolling and has a large amount of good farming land and is also well watered by numerous springs and by Birch Creek which flows North through the Township. It is, however, dry in many places at this season of the year but this is an unusually dry season. Rainy season there is plenty of water in it.</p> <p>There is generally a heavy body of cotton wood and birch timber on the creek bottoms.</p> <p>There are at least 50 settlers in this Township.</p>
	<p>Subdivisions of T. 1 N., R. 32 E. Surveyed by Z. F. Moody under contract No. 164. Dated October 4, 1871.</p>
	<p>North between secs. 35 and 36.</p> <p>40.00 Set stone, 18 x 14 x 7, for $\frac{1}{4}$ sec. cor.</p> <p>80.00 Set post and made earth mound for cor. to secs. 35, 36, 25 and 26.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p>
	<p>East on random between secs. 25 and 36.</p> <p style="text-align: right;">Var. 20° 30' E.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor.</p> <p>80.14 Intersected N. and S. line at corner.</p> <p>West on true line.</p> <p>40.07 Set post and made earth mound for $\frac{1}{4}$ sec. cor.</p> <p>80.14 To corner.</p> <p>Land, level.</p> <p>Soil, good.</p>
	<p>North between secs. 25 and 26.</p> <p>40.00 Set post and made earth mound for $\frac{1}{4}$ sec. cor.</p> <p>80.00 Set stone, 20 x 18 x 14, for cor. to secs. 25, 26, 23 and 24.</p> <p>Land, level.</p>