

Subdivisions of T. 1 N., R. 32 E.

Chains	South on true line.
16.40	Howetome creek, N.W. and S.E.
22.10	Same creek.
29.70	Leave creek.
40.50	Set post for $\frac{1}{4}$ sec. cor. from which A balm, 20 ins. diam., bears N. 10° E. 100. " " 10 " " " N. 60° W. 343.
80.50	To corner. Land, level. Soil, 1st rate. November 10, 1871.
Exterior Lines of T. 1 N., R. 32 E. Surveyed by Zenas F. Moody under contract No. 164. Dated October 4, 1871.	
	North on East boundary of sec. 36.
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. corner.
80.00	Set post and made earth mound for cor. to secs. 25, 36, 30 and 31. Land, rolling. Soil, good.
	North on East boundary of sec. 25. Var. 20° East.
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. cor.
80.00	Set post and made earth mound for cor. to secs. 24, 25, 19 and 30. Land, rolling. Soil, good.
	North on East boundary of sec. 24. Var. 20° 30' E.
40.00	Set stone, 14 x 12 x 9, for $\frac{1}{4}$ sec. cor.
80.00	Set post and made mound of earth for corner to secs. 13, 24, 18 and 19. Land, rolling. Soil, good.