

## Subdivisions of T. 1 N., R. 32 E.

Chains	Soil, 1st rate. Poor grass and sage brush.	
	West on random between secs. 14 and 23. Var. 20° 30' East.	
40.00	Found old $\frac{1}{4}$ sec. cor., which is a post firmly set in the ground in mound of earth with pits E. and W. of post. Thence East on true line.	
3.00	Intersect U. R. bdy. Set stone, 10 x 10 x 10 ins., 7 ins. in the ground for U. R. Closing cor. marked U R C C on E. face. Dug pits, 18 x 18 x 12 ins., E., N. and S. from cor. $5\frac{1}{2}$ ft. dist. I raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.	
10.00	McKay Creek, 50 lks. wide, runs N.	
23.00	Spring branch, 2 lks. wide, runs. N.W.	
40.00	To cor. to secs. 13, 14, 23 and 24. Land, mostly level bottom, some gravel. Soil, 2nd rate. Cottonwood and thorn along creek. Grass, poor.	
	North on true line between secs. 13 and 14. Var. 20° 30' East.	
39.25	Set stone, 18 x 10 x 8 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face; dug pits, 18 x 18 x 12 ins., N. and S. from stone, $5\frac{1}{2}$ ft. dist. I raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
49.50	Bottom of hollow, course W.	50
56.50	Summit of hill, course W.	80
73.10	Wagon Road, course N.E.	
78.50	To old cor. Set stone, 7 x 8 x 9 ins., 6 ins. in the ground for cor. to secs. 11, 12, 13 and 14 marked with 4 notches on S. and 1 on E. edges. Dug pits, 18 x 18 x 12 ins., in each sec. $5\frac{1}{2}$ ft. dist. and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Land, rolling.	