

Subdivisions of T. 1 N., R. 32 E.

Chains	
	Grass, poor.
	North on random line between secs. 2 and 3. Var. 20° 30' East.
40.00	Set temp. $\frac{1}{4}$ sec. cor.
80.50	Intersect Township line, 40 lks. E. of cor. to secs. 2, 3, 34 and 35. Thence S. 17' East on true line. Var. 20° East.
13.00	McKay Creek, 50 lks. wide, runs N.W.
40.50	Set basalt stone, 8 x 10 x 14 ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face from which A balm, 24 ins. diam., bears N. 20° W. 1.20 chs. dist. marked $\frac{1}{4}$ S B T. No other trees within limits. Raised a mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.
80.50	To cor. to secs. 2, 3, 10 and 11. Land, rolling. Considerable underbrush in bottom consisting of thorn and willow. Soil, 1st rate.
	West on random between secs. 3 and 10. Var. 20° 30' East.
40.00	Set temp. $\frac{1}{4}$ sec. cor.
80.00	Intersect W. bdy., 7 lks. S. of cor. to secs. 3, 4, 9 and 10. Thence S. 89° 57' East on true line. Var. same.
8.00	Leave Birch Creek bottom and ascend.
22.00	Enter field.
35.00	Intersect U. R. bdy. and set a stone, 10 x 10 x 12 ins., 8 ins. in the ground for U. R. closing cor. marked U R C C on E. face. Dug pits, 18 x 18 x 12 ins., E., N. and S. from stone, $5\frac{1}{2}$ ft. dist. and raised a mound