

Exterior Lines of T. 2 N., R. 32 E.
 Surveyed by James P. Currin and James E. Noland, special contrac
 Dated May 4, 1887.

Chains		
	Beginning at the cor. to secs. 3, 4, 33 and 34, on line between Tps. 1 and 2 N., R. 32 East which is a post in mound with pits and trench I run East on random between secs. 3 and 34, retracing old line. Var. 19° E.	
40.00	Set temp. $\frac{1}{4}$ sec. cor.	
79.70	I found old mound and pits to cor. to secs. 2, 3, 34 and 35, 25 lks. S. of line. I set a basalt stone, 18 x 12 x 12 ins. in old mound, 12 ins. in the ground, marked 2 notches on E. and 4 on W. edges. Renewed the pits and raised earth mound 2 ft. high, $4\frac{1}{2}$ ft. base alongside. Thence I run S. 89° 50' W. on true line between secs. 3 and 34.	
16.00	McKay Creek, 40 lks. wide, N.	
24.15	Fence runs N.W.	
25.00	Wagon road, N.W.	
39.70	Found old mound for $\frac{1}{4}$ sec. cor. Set a basalt stone, 9 x 8 x 7 ins., 12 ins. in old mound marked $\frac{1}{4}$ on N. face, made new pits E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised earth mound $1\frac{1}{2}$ ft. high, and $3\frac{1}{2}$ ft. base alongside.	
51.00	Summit of hill.	+100
54.00	Gulch, course N.	-75
73.70	Intersect U.R. bdy. set a basalt stone, 16 x 12 x 8 ins., 12 ins. in the ground for closing cor. to Tps. 1 and 2 N., R. 32 E. ; dug pits, 18 x 18 x 12 ins., N., E. and S. of stone, $5\frac{1}{2}$ ft. dist. raised earth mound 2 ft. high, $4\frac{1}{2}$ ft. base alongside. (Marked stone U R C C)	
79.70	To cor. to secs. 3, 4, 33 and 34. Land, rolling. Soil, white ashy. and gravelly. Some bunch grass.	
	East on random between secs. 2 and 35. Var. 20° 30' E.	
40.00	Set temp. $\frac{1}{4}$ sec. cor.	