

Subdivisions of T. 1 North, R. 33 E.

Chains 64.30	Top of hill, bears E. and W.; descend.	+700
80.00	Set stone, 18x16x12, for corner to secs. 14, 15, 22 and 23, on steep hill-side. Land, steep and stony. Soil, 3rd rate.	-400
North between secs. 14 and 15. Var. 21° E. Descend hill.		
19.50	Ravine, bears West. Foot of hill; ascend.	
40.00	Set stone, 12x12x8, for $\frac{1}{4}$ sec. cor.	-400
54.00	Top of hill; descend.	+400
80.00	Set post for corner to secs. 10, 11, 14 and 15 in mound of earth with charred stake, pits &c as per instructions. Land, hilly. Soil, 2nd rate.	-250
North between secs. 10 and 11. Var. 18 $\frac{3}{4}$ ° E. Descend hill.		
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.	
80.00	Set stone, 18x12x10, for corner to secs. 2, 3, 10 and 11 Foot of hill. Land, hilly, sloping NW. Soil, 2nd rate.	-700
North on a random line between secs. 2 and 3. Var. 19° E.		
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
80.57	Intersect North boundary 47 lks. East of corner to secs. 2 and 3, from which I run S.0°20'E. on a true line.	
40.57	Set stone, 16x10x10, for $\frac{1}{4}$ sec. cor.	
80.00	Dry bed of creek runs NW.	
80.57	The corner to secs. 2, 3, 10 and 11. Land, level. Soil, 1st rate.	
November, 28, 1864.		