

Subdivisions of T. 1 N., R. 33 E.

Chains	East on a random line between secs. 22 and 27.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.	
79.68	Intersect N. and S. line, 69 lks. North of corner to secs. 22, 23, 26 and 27, from which corner I run N.89°30'W. on a true line between secs. 22 and 27. Descend hill.	
39.84	Set stone, 18x10x6, for $\frac{1}{4}$ sec. cor.	
79.68	The corner to secs. 21, 22, 27 and 28. Land, rolling, sloping West. Soil, 2nd rate.	-300
	North between secs. 21 and 22. Var. $19\frac{1}{2}$ °E. Descend hill.	
40.00	Set stone, 16x12x6, for $\frac{1}{4}$ sec. cor.	
80.00	Set post for corner to secs. 15, 16, 21 and 22 in mound of earth with charred stake, pits &c as per instructions. Land, rolling. Soil, 2nd rate.	-200
	East on random line between secs. 15 and 22.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.	
79.74	Intersect N. and S. line, 63 lks. North of corner to secs. 14, 15, 22 and 23, from which I run N.89°43'W. on a true line between secs. 15 and 22. Descend West slope of mountain.	
39.87	Set stone, 17x8x6, for $\frac{1}{4}$ sec. cor.	
79.74	The corner to secs. 15, 16, 21 and 22. Land, hilly on west slope of mountain. Soil, 2nd rate.	-400
	North between secs. 15 and 16. Var. $19\frac{1}{4}$ °East. Descend hill.	
25.00	Foot of hill.	-100