

## Subdivisions of T. 1 N., R. 33 E.

Chains 80.50	The corner to secs. 3, 4, 9 and 10. Land, level. Soil, 1st rate.	
	North on a random line between secs. 3 and 4. Var. 20°E.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.	
79.35	Intersect North boundary, 57 lks. West of corner to secs. 3 and 4, from which I run S.0°24'W. on a true line between secs. 3 and 4.	
39.35	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.	
79.35	The corner to secs. 3, 4, 9 and 10. Land, level. Soil, 1st rate.	
	North between secs. 32 and 33.	
20.00	Descend hill.	
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.	+200
80.00	Set post for corner to secs. 32, 33, 28 and 29 in mound of earth with charred stake, pits &c as per instructions. Land, hilly. Soil, 2nd rate.	-400
	November 29, 1864.	
	East on a random line between secs. 28 and 33.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.	
80.00	Intersect N. and S. line, 42 lks. North of corner to secs. 27, 28, 33 and 34, from which I run N.89°42'W. on a true line between secs. 28 and 33.	
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.	
80.00	The corner to secs. 28, 29, 32 and 33. Land, gently rolling. Soil, 1st rate.	